



# GREEN LINKS MASTERPLAN

## Ryde | Eastwood | Macquarie Park

### Masterplan Report

ADOPTED BY COUNCIL

26 JULY 2022





Proudly funded by the NSW Government in association with the City of Ryde Council.

---

Revision:	Status:	Date:	By:	Checked:
A	Initial Draft for Council Review	15.10.21	LP/AM	LP
B	Draft for Stage 2 Community Consultation	20.12.21	AM	LP
C	Draft for adoption by Council	30.06.22	AD/LP	LP
D	Report to Council Adopted with amendment	26.07.22	AD/LP	LP
E	Final Masterplan with adopted amendments	03.08.22	AD	LP

---

**Project Client:** City of Ryde  
**Project Name:** Green Links Masterplan  
**Project Number:** 0837SYD  
**Date:** 03.08.22

---

**Studio:** Sydney  
**Report Contact:** Logan Pennington, Senior Landscape Architect, McGregor Coxall  
**Council Contact:** Meredith Gray, Open Space Planner, City of Ryde

---



## AUSTRALIA

### Sydney

Phone: +61 [0]2 9188 7500  
Email: [sydney@mcgregorcoxall.com](mailto:sydney@mcgregorcoxall.com)  
Address: Suite 101, Level 1, 39 East Esplanade, Manly NSW 2095, Australia.

### Melbourne

Phone: +61 [0]3 9088 6500  
Email: [melbourne@mcgregorcoxall.com](mailto:melbourne@mcgregorcoxall.com)  
Address: Level 4, 125 Flinders Lane, Melbourne VIC 3000, Australia.

## CHINA

### Shenzen

Email: [shenzen@mcgregorcoxall.cn](mailto:shenzen@mcgregorcoxall.cn)  
Address: 9D/9thflr, Shenzhen Zimao Ctr, 111 Taizi Rd, Nanshan District, Shenzhen, China

## UNITED KINGDOM

### Bristol

Phone: +44 [0]7496 282281  
Email: [bristol@mcgregorcoxall.com](mailto:bristol@mcgregorcoxall.com)  
Address: 77 Stokes Croft, Bristol BS1 3RD, United Kingdom.

[www.mcgregorcoxall.com](http://www.mcgregorcoxall.com)

---

## DISCLAIMER

This Study is for the confidential use only of the party to whom it is addressed [the client] for the specific purposes to which it refers. We disclaim any responsibility to any third party acting upon or using the whole or part of its contents or reference there to that may be published in any document, statement or circular or in any communication with third parties without prior written approval of the form and content in which it will appear. This Study and its attached appendices are based on estimates, assumptions and information sourced and referenced by McGregor Coxall and its sub consultants. We present these estimates and assumptions as a basis for the reader's interpretation and analysis. With respect to forecasts we do not present them as results that will actually be achieved. We rely upon the interpretation of the reader to judge for themselves the likelihood of whether these projections can be achieved or not. If financial models have been included, they have been prepared from the best information available at the time of writing, no responsibility can be undertaken for errors or inaccuracies that may have occurred both with the programming or the financial projections and their assumptions. In preparing this Study we have relied upon information concerning the subject property and/or study area provided by the client and we have not independently verified this information except where noted in this Study.

# Contents

<b>1.0</b>	Introduction .....	5
1.1	Introduction .....	6
1.2	Project Program.....	7
<b>2.0</b>	Masterplan Strategies.....	9
2.1	Green Transport Overview.....	12
2.2	Environment Overview .....	20
2.3	Recreation & Culture / Community Overview	28
<b>3.0</b>	Masterplan .....	37
	Shrimptons Creek Green Link .....	37
3.1	Meadowbank / West Ryde Precinct .....	40
3.2	Santa Rosa Precinct.....	50
3.3	Macquarie Park Precinct.....	62
<b>4.0</b>	Masterplan .....	69
	County Green Link.....	69
4.1	Woorang Precinct.....	72
4.2	Eastwood Precinct.....	80
<b>5.0</b>	Masterplan .....	85
	Terry's Creek Green Link.....	85
5.1	Pembroke Precinct.....	88
5.2	Browns Waterhole Precinct .....	96
5.3	Interconnection - Browns Waterhole and Macquarie Park .....	104
<b>6.0</b>	GIS Analysis .....	113
<b>7.0</b>	Precedent Images & .....	119
	Design Guidelines .....	119
7.1	Planting Palette.....	120
7.2	Materials Palette .....	128
<b>8.0</b>	Implementation Plan .....	137
8.1	Implementation Plan.....	138
<b>9.0</b>	Appendix A.....	148
9.1	Shrimptons Creek Green Link (Blaxland Road - Quarry Road) Sections/ Plans not adopted by Council (26.07.2022). .....	149



# 1.0 INTRODUCTION



# 1.1 Introduction

## Overview

The Ryde - Eastwood - Macquarie Park Green Links will be three interconnected urban green corridors, which will function as biodiversity corridors, provide continuous green transport connectivity along activated open spaces, with cultural engagement and recreation opportunities for the community.

The vision for the Ryde - Eastwood - Macquarie Park Green Links Masterplan combines both the Greater Sydney Commission vision and Council's vision, utilising the open space networks to achieve the broader vision for the City of Ryde to create a diverse, vibrant, healthy, resilient and connected city, in which nature and history is protected and celebrated. The vision for the Green Links Masterplan is to create:

*“recognisable environmental, cultural and green transport corridors linking two of Sydney’s most important rivers and connecting the City of Ryde’s town centres”*

This Masterplan has been developed via a 'whole of government' approach, working with multiple landowners and key stakeholders. Funding for the Masterplan project has been provided by the NSW Government, Department of Planning Industry and Environment [DPIE], via the Metropolitan Greenspace Program, and has been prepared with in principal support from Transport for NSW and Sydney Water.

## Green Links Masterplan

The Green Links Masterplan project is made up of two phases:

### Phase 1: Context Analysis Report

The Context Analysis Report introduces the project background, site context, and an overview of the three Green Link corridors:

- Shrimptons Creek Green Link: will form an open space corridor connecting Macquarie Park and West Ryde, running from north-east to south-west through the centre of the City of Ryde and onwards to Meadowbank.
- County Green Link: will form a connection between Macquarie Park and Eastwood via Marsfield.
- Terrys Creek Green Link: is located on the north-western boundary of the City of Ryde, between Eastwood and Epping. This Green Link will form a connection between Macquarie Park and Eastwood via Lane Cove National Park.

The report outlines the overall vision for the Masterplan and key objectives based on the consolidation of previous Greater Sydney and City of Ryde planning documents. These objectives were used to create a design framework in which part two [Masterplan Report] utilises.

### Phase 2: Masterplan Report [this report]

This Masterplan is a long-term strategic plan which sets the direction for the development of the Ryde - Eastwood - Macquarie Park Green Links. Developing from Phase 1 and responding to feedback from the community of City of Ryde, this report proposes a holistic strategy and Masterplan for each Green Link while integrating other future masterplanning initiatives throughout the City of Ryde local government area.

This Masterplan Report:

- Summarises the analysis and findings from the Context Analysis Report
- Explains the purpose of this Masterplan
- Summarises the key findings from the community consultation
- Introduces the Masterplan strategies and subsequent objectives, relating to environment, green transport, recreation and recreation & culture / community and how they are applied to each of the three Green Link corridors
- Provides an overview of the existing character and features of each Green Link corridors [Shrimptons Creek, County & Terrys Creek] and their precincts
- Presents the Masterplan for each precinct, including proposed character
- Summarises the proposed implementation strategy for the Masterplan
- Outlines the priority projects for each Green Link corridor.

The Context Analysis Report and this Masterplan Report [phase 1 & 2] will be the principal plan guiding the implementation of physical elements of the Green Links, both built and natural.

# 1.2 Project Program



## Green Links Masterplan




This Masterplan is a high level strategic vision and overview, which is subject to adoption by Council and subject to consideration and specific impacts by the applicable land owners [e.g. Transport for NSW, Sydney Water, Department of Planning, Industry and Environment, and National Parks and Wildlife Service].

Detailed design, including technical reports, analysis and approvals processes [where required], will be undertaken as next steps in the implementation of Masterplan stages. Where required, this will be done in consultation and with the applicable land owners [as mentioned above]. The Green Links Masterplan will be progressively implemented over a 20 year period (subject to funding availability). Refer to Section 7 - Implementation Plan for additional information.



## 2.0 MASTERPLAN STRATEGIES



## Objectives


The Green Links Masterplan objectives and strategies are drawn from and guided by the objectives and actions of the following key strategic planning and strategy documents, and informed by consultation with key stakeholders:

- Greater Sydney Commission Metropolis of Three Cities [2018]
- Greater Sydney Commission North District Plan [2018]
- Greater Sydney Commission Green Grid North District Plan [2017]
- City of Ryde Local Planning Statement 2020 [2020]
- City of Ryde 2028 Community Strategic Plan [2018]
- City of Ryde Biodiversity Plan [2016]
- City of Ryde Bicycle Strategy [Draft - 2022]
- City of Ryde Bicycle Strategy [2014]
- City of Ryde Sustainable Transport Strategy [2022]
- City of Ryde Sport and Recreation Strategy [2017]
- City of Ryde Integrated Transport Strategy [2022]
- City of Ryde Resilience Plan 2030 [2020]
- NSW Department of Planning, Industry and Environment Macquarie Park Place Strategy [Draft 2021]
- Greater Sydney Commission Meadowbank Education and Employment Precinct Masterplan [2019]
- City of Ryde park and town centre Masterplans (various)
- Discussion with the City of Ryde and other stakeholders during development of this Masterplan

The objectives of the Green Links Masterplan are detailed on the following page. The importance of each objective in relation to specific Green Link corridors has been identified and will guide the implementation plan and priority projects.

## Implementation

An implementation plan has been developed as part of this Masterplan for continued and progressive delivery of the Green Links over the next 20 years. The implementation plan will prioritise implementation of key projects [priority projects] based on strategic importance, community feedback, cost and available funding. These implementation priority projects can be found in Section 7.



The Green Links objectives have been organised into four themes, and this diagram illustrates the relationship between these themes. Ecology and Green transport are both ideas that need connectivity along the corridors and create the “spines” of the Green Links; recreation and culture build on this spine, activating places along the corridor.

## Strategic Importance

The Green Links will be a benchmark of blue and green infrastructure that supports habitats and important ecological processes in an urban setting, as well as addressing the local pressures on traffic and public transport, open space, demands for recreation, cultural experience and greater diversity of recreation opportunities.

The Green Links also have the potential to be an exemplar of the Green Grid due to its strategic location between Lane Cove River and Parramatta River, providing connection to education facilities, major business centres [e.g. Macquarie Park and Parramatta] and urban renewal corridors; and its commitment to achieve multiple objectives including ecological, green transport, recreation and cultural objectives.

These four main thematic objectives return throughout this Masterplan:

**Environment:** the Green Links as blue and green biodiversity corridors

**Green Transport:** the Green Links as transport corridor

**Recreation:** the Green Links as a place that meets multiple recreational needs

**Culture & Community:** the Green Links as a focal point for community and culture

Green Links Objectives		Importance [high/medium/low]		
		Shrimptons Creek Green Link	County Green Link	Terrys Creek Green Link
<b>Environment</b>	– protect and enhance natural areas including bushlands, waterways and ecosystems	high	medium	high
	– manage and mitigate effects of climate change on people and ecology [green grid]	high	high	high
	– collaborate with volunteers [bush care groups], businesses and the community to care for and enhance natural areas.	high	medium	high
<b>Green Transport</b>	– create safe, continuous and permeable active transport corridors with connections to the surrounding networks	high	high	low
	– explore connectivity and interconnectivity with current and future mass transport options	low	high	low
	– enhance and maintain connections and accessibility to centres, open spaces and places, including improved cycleways and walkways.	high	high	medium
<b>Recreation</b>	– deliver a series of interconnected, high quality open spaces that encourage active lifestyles and social interaction	high	high	medium
	– integrate a range of active and passive recreation opportunities for the community to meet, play, learn and connect.	high	high	medium
<b>Culture &amp; community</b>	– celebrate cultural diversity and promote inclusion	high	high	medium
	– protect, enhance and interpret cultural heritage	high	medium	medium
	– use the Green Links for educational purposes and to share stories and information.	high	high	high
	– provide places that support events	high	medium	low
	– create and enhance community infrastructure along the Green Links and enhance amenity value, design quality, identity and sense of place	high	high	medium

## 2.1 Green Transport Overview

The vision for green transport in the City of Ryde has two key layers. At the City of Ryde local government area scale, the vision is to be regionally connected and locally accessible with “a traffic and transport system that supports economic growth and local amenity by stimulating land development, influencing the use of sustainable transport and promoting safety and equity.” City of Ryde Integrated Transport Strategy 2016-2031 [2016].

The Green Links Masterplan’s strategic direction to promote a shift in transport from private vehicles to more efficient modes of walking, cycling and public transport within the City of Ryde local government area is consistent with the NSW Future Transport Strategy.

Connect Macquarie Park Innovation District is a business led organisation who are currently active in encouraging the community to change their travel behaviour. The shift in modes of transport and travel behaviour will increase the efficiency of transport systems, reduce traffic congestion and decrease drive-alone vehicle travel for the journey to work in Macquarie Park and North Ryde. Critical to this ambition is promoting cycling and improved cycleways and mass transport connections. Responding to this green transport vision the Masterplan will reflect Council’s priority by:

### Improved access to suburbs, workplaces and major destinations:

- Promoting sustainable transport and reducing reliance on cars

- Improve connectivity and interconnectivity with current mass transport options within the City of Ryde and beyond
- Plan for improved connectivity and interconnectivity via future potential micro-mobility technologies options within the City of Ryde and beyond (refer to following page)


### Improving access to local centres, recreation assets and reduce the travel footprint:

- Planning for increased use of active and public transport options, and improved pedestrian access and mobility
- Continuing investment in the road network, footpaths, cycleways and walkways

The following diagrams overleaf provide a high level detailed analysis of the three Green Link corridors based on the theme of green transport. This analysis will assist in the understanding of gaps, opportunities and future improvements for each corridor.

The Green Link Masterplan will provide significantly enhanced connection to mixed modes of mass transport including:

- Train [Eastwood, West Ryde, Meadowbank and Epping]
- Metro [Macquarie Park and Macquarie University]
- Ferry [Meadowbank]
- Bus [local routes regional bus routes along Epping Road, Victoria Road and Lane Cove Road, as well as hubs at Macquarie Park, Eastwood, West Ryde and Meadowbank]
- Light rail [future: Melrose Park - Stage 2 extension Sydney Olympic Park to Parramatta]




Regional active transport links [based on: City of Ryde Cycling Orbitals [2018]; Open Street Map [2020]]




At the time of writing this report (June 2022) the NSW Government was seeking to commence a shared scheme e-scooter trial in NSW. This emerging micro-mobility technology may contribute to improving liveability, productivity and sustainability. The parameters for this trial and future use of e-scooters in NSW is currently being developed.

technologies, such as e-scooters, within permissible domains within the City of Ryde and the Green Links corridors. This may potentially need to include consideration of docking/recharging stations, widths and/or configurations of shared user paths/cycleways, identification of 'slow' zones and 'no-go' zones. If/where required, this may need to be considered during detailed design stages of Masterplan implementation, in consultation with relevant authorities and in accordance with government directions and applicable legislation.

Existing and future facilities/infrastructure may potentially need to accommodate e-bikes and other future forms of micro-mobility




Active transport



-  School
-  Macquarie University
-  New school/ education precinct/ Tafe
-  Town centres
-  On-road bike lane
-  Green Link crossings (safe/moderate/unsafe)
-  Public parkland
-  Informal on-road bike route
-  ~5% gradient
-  5-10% gradient
-  Off-road shared path
-  Off-road mountain bike route
-  10-15% gradient
- >15% gradient icon" data-bbox="798 912 928 926"/> >15% gradient

Active Transport map [based on: City of Ryde Bike Map [2020]]

# Shrimptons Creek Green Link - Green Transport Overview



- Shrimptons Creek Green Link: Shared User Path/ Cycle Path
- On road: Green Links Interconnection
- On road: Potential cycle connection
- County Green Link: Shared user path
- On road: east-west cycle connections
- Green Link gateway node
- Significant road intersection
- Existing on road bike network




- M2 Motorway
- Trunk Road
- Primary Road
- T Train Station
- Railway
- F Ferry Wharf
- M Metro Station
- Metro: Underground
- B Bus Interchange


Scale 1:15 000



# County Green Link - Green Transport Overview



- County Green Link: Shared user path
- Terrys Creek Green Link: Track/path
- Shrimptons Creek Green Link: Shared User Path
- On road: Green Links Interconnection
- On road: Potential cycle connection
- On road: east-west cycle connections
- Green Link gateway node
- Significant road intersection
- Existing on road bike network




- |              |                 |                                    |
|--------------|-----------------|------------------------------------|
| M2 Motorway  | Train Station   | Metro Station                      |
| Trunk Road   | Railway         | Metro: Underground                 |
| Primary Road | Bus Interchange | Existing off-road shared user path |


Scale 1:10 000



# Terrys Creek Green Link - Green Transport Overview



- Terrys Creek Green Link: Track/path
- County Green Link: Shared user path
- On road: Green Links Interconnection
- On road: Potential cycle connection
- On road: east-west cycle connections
- Green Link gateway node
- Significant road intersection
- Existing on road bike network



- |  |   |  |
|--|---|--|
|  M2 Motorway  |  Train Station   |  Metro Station                            |
|  Trunk Road   |  Railway         |  Metro: Underground                       |
|  Primary Road |  Bus Interchange |  Existing off-road shared user path [SUP] |

Scale 1:10 000



## 2.2 Environment Overview

Throughout the City of Ryde's consultation for the preparation of the 2028 Community Strategic Plan [2018], *'people emphasised the city's natural environment, green open spaces and parks as the thing they love the most about Ryde.'* Protecting bushland and open space and expanding green spaces, tree coverage, parks and their facilities are therefore key priorities for the community of the City of Ryde.

In accordance with the vision of community of the City of Ryde as outlined in the 2028 Community Strategic Plan and the vision in the Ryde Biodiversity Plan [2016], this Masterplan will:

*"demonstrate environmental and sustainability leadership and assist in the management, enhancement and protection of natural areas and biodiversity along the Ryde - Eastwood - Macquarie Park Green Links."*

This Masterplan will reflect Council's priority to:

### Protect natural areas:

- Reduce impacts on natural systems including waterways, soil and native vegetation
- Strengthen the health of natural corridors
- Promote complementary native plantings [including mid-storey and under-storey] with habitat values within the Green Links corridors, interconnections and adjoining developments to strengthen biodiversity corridors

- Promote responsible use and protection of natural areas [including wildlife protection areas along Terrys Creek and within the Lane Cove National Park]


### Promote resilient green infrastructure:

- Address long term climate-related risks and impacts including: extreme weather patterns, bushfires, drought, flooding and a changing climate


### Promote sustainable living:

- Reduce environmental footprint
- Connect people to nature through walking and cycling journeys
- Interpret the natural values and environmental stewardship projects within the corridor to educate the community and encourage involvement and collaboration
- Demonstrate the City of Ryde's role as active environmental leaders in ecologically sustainable development
- Enhance environmental stewardship through collaboration with volunteers groups such as bushcare, citizen science programs, tree planting days and business sponsorship and participation

The following diagrams overleaf provide a high level detailed analysis of the three Green Link corridors based on the theme of environment. This analysis will assist in the understanding of gaps, opportunities and future improvements for each corridor.



Environmentally Sensitive Land Structure Plan [source: City of Ryde Local Strategic Planning Statement [2020]]




Legend



- - - Bushfire prone land (incl. buffer zones)
- Flood risk land
- - - Green Links boundary
- Green space / parkland
- Riparian corridors
- - - Regional ecological connections
- - - Local ecological connections
- - - Opportunities for ecological connections

Ecological constraints and opportunities for connectivity [based on: City of Ryde Bushfire Prone Land Map [2017], City of Ryde Flood Risk Map [2016]; City of Ryde Local Strategic Planning Statement [2020]; City of Ryde Biodiversity Plan [2016]]

# Shrimptons Creek Green Link - Environment Overview




- Local open space
- Regional open space
- District open space
- Poor canopy cover
- Medium canopy cover
- High canopy cover
- Road crossing: Disconnected Biodiversity corridor




Scale 1:15 000



# County Green Link - Environment Overview



- Local open space
  - Regional open space
  - District open space
- Poor canopy cover
  - Medium canopy cover
  - High canopy cover
- Road crossing:  
Disconnected Biodiversity corridor




Scale 1:10 000



# Terrys Creek Green Link - Environment Overview



- Local open space
- Regional open space
- District open space
- Poor canopy cover
- Medium canopy cover
- High canopy cover
- Road crossing:  
Disconnected Biodiversity corridor



Scale 1:10 000



## 2.3 Recreation & Culture / Community Overview

### Recreation Overview

In this Masterplan ‘recreation’ refers to all outdoor recreational activities, including active sports and leisure. The Ryde community have expressed that their open spaces, recreation and sporting facilities are very important to them and are critical for the community living an active and healthy lifestyle. In the context of significant projected population growth, it is essential for Council to provide for sport and recreation with facilities and programs that are flexible and adaptable to these changing community needs, expectations and growing demands.

The Green Links will play a significant role in contributing to a diverse recreational experience for the community through the following key objectives:

- The delivery of a series of interconnected, high quality open spaces that encourage active lifestyles and social interaction
- Integrate a range of active and passive recreation and sporting opportunities for the community to meet, play, learn and connect
- Optimise existing and new sport / recreation facilities to maximise use to better meet the growing demands

Sport and recreation are key elements to the lifestyle of Ryde residents. Council’s vision, as outlined in the Sport and Recreation Strategy [2017] is:

*“Through its role in sport and recreation planning and management, the City of Ryde will contribute to the lifestyle, health and wellbeing and social cohesion of the community.”*


Additionally, Council’s commitment to the open space network is to ensure that:

*“...we have ample accessible open space to meet our needs, shared and enjoyed by us all, founded on a healthy natural environment, conserving our rich history, culture and local character and managed sustainable now and for future generations.”*

The results from Council’s previous community consultation for the City of Ryde Community Strategic Plan [2018], has made it clear that people love the city’s green spaces and parks, and value the range of services, programs and recreational facilities available to them.

Key recommendations following community consultation for the Sports and Recreation Strategy 2016-2026 are:

- Provision of additional informal leisure and recreation facilities or settings [i.e. Open spaces, bike paths, walking paths and tracks, dog exercise areas, youth facilities, skate parks]
- A multi-disciplinary approach to planning, design and management of informal leisure and recreation facilities or venues
- The requirements of organised sporting groups are balanced with the needs of informal/ independent participants
- Investigating improved transport and access services for leisure and recreation, particularly where seniors are concerned
- Continuing consultation regarding the needs of all residents



Open Space Structure Plan [source: City of Ryde Local Strategic Planning Statement [2020]]

## Culture / Community Overview

In this Masterplan 'culture & community' refers to the social and cultural infrastructure, including community facilities and activities, art and cultural heritage.

In accordance with the vision of the City of Ryde, as outlined in the Ryde Local Strategic Planning Statement [2020], this Masterplan will ensure that:

*"Heritage and places of cultural significance that are valued by the community – including historic buildings, landscape items and places with natural and Aboriginal significance – will be well managed, conserved and positively promoted to enhance the community's sense of place."*

*"Social and cultural infrastructure [including libraries, community services and events] will be strategically located to ensure all community members can enjoy them."*

This Masterplan will reflect community priorities [as outlined in the City of Ryde Community Strategic Plan [2018]], including:

### An engaged, connected community

- Optimise existing and new community facilities and access to these facilities to maximise use to better meet growing demands
- Working with stakeholders, partners and the community to support all members of the community and promote social inclusion

- Through our community network and with State agencies, appropriately supporting all members of the community and providing access to available services and facilities


### Celebrating culture and heritage

- Continuing to enhance our events program to provide opportunities to celebrate diversity and heritage and promote inclusion
- Protect, enhance and interpret cultural heritage
- Provide places that support events

### Accessible community facilities

- Planning for and enhancing cultural and community facilities to meet increased demand and ensure equitable access for all sections of the community
- Create and enhance community infrastructure along the Green Links and enhance amenity value, design quality, identity and sense of place

The following diagrams overleaf provide a high level detailed analysis of the three Green Link corridors based on the theme of recreation and community / culture. This analysis will assist in the understanding of gaps, opportunities and future improvements for each corridor.





City of Ryde Community Facility Structure Plan [source: City of Ryde Local Strategic Planning Statement [2020]]

# Shrimptons Creek Green Link - Recreation & Community / Culture Overview



- |                  |                       |               |                               |
|------------------|-----------------------|---------------|-------------------------------|
| Retail           | Golf course           | Business Park | Cricket/Rugby/Soccer/Baseball |
| Commercial       | Park                  | Mixed use     | Playground                    |
| Health/Education | Bushland/nature areas | Industrial    | Place of worship              |



- Basketball/Netball/Court
- AFL/Oval
- Hockey Field
- Bowling Green / Croquet
- Half Court
- Community Hall
- Dog Recreation Area
- Library
- Cinema / Theatre


Scale 1:15 000



## County Green Link - Recreation & Community / Culture Overview



- |                  |                       |               |                               |
|------------------|-----------------------|---------------|-------------------------------|
| Retail           | Golf course           | Business Park | Cricket/Rugby/Soccer/Baseball |
| Commercial       | Park                  | Mixed use     | Playground                    |
| Health/Education | Bushland/nature areas | Industrial    | Place of worship              |



- Basketball/Netball/Court
- AFL/Oval
- Hockey Field
- Bowling Green/Croquet
- Half Court
- Community Hall
- Dog Recreation Area
- Library
- Cinema / Theatre


Scale 1:10 000



# Terrys Creek Green Link - Recreation & Community / Culture Overview



- |                  |                       |               |                               |
|------------------|-----------------------|---------------|-------------------------------|
| Retail           | Golf course           | Business Park | Cricket/Rugby/Soccer/Baseball |
| Commercial       | Park                  | Mixed use     | Playground                    |
| Health/Education | Bushland/nature areas | Industrial    | Place of worship              |



- |                            |                         |                       |
|----------------------------|-------------------------|-----------------------|
| ○ Basketball/Netball/Court | ○ Bowling Green/Croquet | ○ Dog Recreation Area |
| ○ AFL/Oval                 | ○ Half Court            | ○ Library             |
| ○ Hockey Field             | ○ Community Hall        | ○ Cinema / Theatre    |

Scale 1:10 000





Artist impression - Shrimptons Creek Green Link at Macquarie Park

# 3.0 MASTERPLAN SHRIMPTONS CREEK GREEN LINK



## Overview

The Shrimptons Creek Green Links is strategically significant for local and regional connection. It will realise a major missing link and strengthen connectivity for active transport, link town centres, education centres (schools and universities) and a diverse range of public transport option (metro, rail, bus and ferry). Shrimptons Creek Green Link will provide a connection between Macquarie Park and Parramatta, which is of major significance regionally and contributes towards realising the Greater Sydney Commission's vision for a connected greater Sydney region for "three cities where most residents live within 30 minutes of their jobs, education and health facilities, services and great places".

The vision for Shrimptons Creek Parklands is to recognise the importance of this creek line as a Green Link. The importance and strategic significance of this creek has been recognised and the proposed Shrimptons Creek Green Link will connect Macquarie Park to West Ryde and more broadly Lane Cove River to Parramatta River with a pedestrian and cycle network.

This Green Link not only provides an active transport route, it also enhances the interconnectedness to neighbouring open spaces and future masterplans, strategies and initiatives developed by the City of Ryde. Adjacent ecological environments and networks will also be improved without compromising their natural character. The Green Link will be maintained and appreciated as a healthy natural area while acting as an ecological buffer to the creek from adjacent urban areas.

## Meadowbank / West Ryde Precinct

Between Blaxland Road to West Ryde and the connection to Ryde River Walk/Parramatta River Valley Cycleway at Meadowbank.

## Santa Rosa Precinct

Between Kent Road to Blaxland Road, including Santa Rosa Park, Tindarra Reserve and Flinders Park. Council resolution on 26 July 2022 excluded the use of the Sydney Water land reservation between Blaxland Road and Quarry Road from the Shrimptons Creek Green Link route.


## ELS Hall

ELS Hall Park has been developed by City of Ryde and captures Greenwood Park and Booth Reserve, the ELS Hall Park Masterplan was developed to balance the needs of the community while protecting and improving local ecologies. The ELS Hall Park, Greenwood Park and Booth Reserve Masterplan [adopted 2019] has been captured in the Santa Rosa Precinct plans.

The Green Links Masterplan will seek to formalise arrangements for "lands not owned by Council" as identified in the ELS Hall Park, Greenwood Park and Booth Reserve Masterplan. These parcels of land are owned by other government agencies. The Green Links Masterplan will seek to formally integrate these into the surrounding parklands.

## Macquarie Park Precinct

Between Waterloo Road to the Epping Road underpass.



**LEGEND**

- Precinct boundary
- Open green space
- Waterways
- Building footprint

## 3.1 Meadowbank / West Ryde Precinct

The Meadowbank / West Ryde Precinct will provide connections from Parramatta River to Blaxland Road. Future pedestrian and cycle connections between the Parramatta River, Meadowbank Train Station and West Ryde Train Station will be captured under the Meadowbank Education and Employment Precinct Masterplan [MEEP]. The MEEP Masterplan will create new opportunities for employment as well as piloting new education models [years K-12]. Enhanced pedestrian and cycle connectivity will be proposed as part of the MEEP Masterplan, these proposals have been highlighted in this precinct. This precinct also includes an open space land reservation owned by Sydney Water from Blaxland Road to Goodwin Street, including Carara Reserve [Sydney Water land].

### Green Transport

From a green transport perspective, the Masterplan ties into the works proposed as part of the MEEP proposal that provide connections towards Parramatta River as well as connections across the railway corridor at Meadowbank and West Ryde Train Stations. From West Ryde Train Station, this Masterplan will provide a continuous pedestrian and cycle link that connects to Blaxland Road. The Masterplan upgrades will include the following:

- Improved cycle connections and greater pedestrianisation between the Ryde River Walk, Meadowbank Wharf and Meadowbank station.
- Off road shared user path along Hermitage Road between Rhodes Street and Herbert Street.
- Upgrades to Ryedale Road included bus zones, raised pedestrian crossings, widening of existing footpath, and bicycle parking facilities at the train station.
- Separated cycle way along Anzac Avenue to provide direct connection between pedestrian/ cycle overpass to MEEP and Blaxland Road.
- Off road shared user path along Wattle Street and active transport link on Herbert Street providing connection between West Ryde Station and Hermitage Road.
- Pedestrian path through the western side of Carara Reserve that continues along Benson Lane. To include path lighting to facilitate safe pedestrian movement beyond daylight hours.
- Signalised intersection at Blaxland Road, Anzac Avenue and Benson Lane to improve existing traffic conditions and provide pedestrian and cycle crossing at Blaxland Road.

### Environment

The Meadowbank / West Ryde Precinct provides opportunity for ecological restoration in a number of locations. These locations include existing facilities and the implementation of new facilities that seek to introduce the following where appropriate:

- additional native trees, shrubs, and grasses to enhance and expand on existing local ecologies.
- WSUD interventions that assist the treatment of local stormwater runoff.



### Recreation & Culture / Community

In this precinct, unlocking the Sydney Water land (Goodwin St - Benson Lane) will promote the activation of Carara Reserve, and provide a continuous pedestrian link. The cycle link from West Ryde Train Station to Blaxland Road will be via Anzac Avenue. The interconnectedness and activation of these open spaces through the implementation of a cycle/ pedestrian path network will provide safe and enjoyable walking/ cycling facilities for the local community.

The Masterplan will assist in a cultural shift from using personal vehicles for local trips to using active modes of transport. Succeeding in this culture shift will result in a healthier community and contribute to a reduction in traffic congestion.

Where applicable designs near Sydney Water assets (eg. Carara Reserve, Santa Rosa Park) will adhere to the following points:

- Where possible, the existing surface levels of the Sydney Water corridor will be retained.
- Shared user paths and/or pedestrian paths are recommended to be asphalt paths.
- The necessary technical reports and assessments will be commissioned during the detailed design phases to ensure the Sydney Water's services, assets and infrastructure are considered and not impacted upon during Masterplan implementation.
- Crime Prevention Through Environmental Design (CPTED) strategies will be implemented to ensure the space is safe and accessible.



Section A - Indicative Anzac Ave separated cycleway



Precedent image - Raised pedestrian / cycle crossings



Precedent image - Separated cycle way




Precedent image - Shared path with lighting




Precedent image - Repair Bike station

# Parramatta River



## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment




# Meadowbank



**LEGEND**

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Waterway
-  Existing Canopy Cover
-  Planting treatment




## Hermitage Road / West Ryde Station




# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Waterway
-  Existing Canopy Cover
-  Planting treatment



## Anzac Avenue / Carara Reserve



## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment



## 3.2 Santa Rosa Precinct

The Santa Rosa Precinct will provide continuous off-road cycle and walking connections from Blaxland Road to ELS Hall Park. ELS Hall Park Masterplan has been developed by City of Ryde and captures Greenwood Park and Booth Reserve. The ELS Hall Park Masterplan was developed to balance the needs of the community while protecting and improving local ecologies. This precinct also includes the activation of an underutilised open space land reservation which will link Blaxland Road to Santa Rosa Park at Quarry Road before continuing through Flinders Park and Tindarra Reserve.

### Green Transport

From a green transport perspective, the implementation of a continuous off-road shared user path will provide a safe and continuous pedestrian and cycle link that includes the following:

- Signalised traffic intersection with pedestrian/ cycle crossing at Blaxland Road/ Anzac Avenue/ Benson Lane [subject to Transport for NSW's consideration and assessment of specific impacts]
- Council resolution on 26 July 2022 excluded the use of the Sydney Water land reservation between Blaxland Road and Quarry Road from the Shrimptons Creek Green Link route.
- Raised pedestrian crossings at Quarry Road and Bridge Road
- Upgraded pedestrian and cycle connections through Santa Rosa Park including enhanced connections to Fawcett Street, Zola Avenue and Kent Road
- Upgrades to existing shared user paths through Flinders Park and Tindarra Reserve with improved connectivity along Ford Street
- Upgrades at Tindarra Reserve will connect to existing pedestrian and cycle facilities at Greenwood Park which provides off-road access to Herring Road to the north-west and Macquarie Park to the north-east.
- Path lighting between Santa Rosa Park to ELS Hall Park to facilitate safe use beyond daylight hours.

To improve pedestrian / cycle safety, the new route in the Masterplan aligns with a new signalised intersection at Blaxland Road, Anzac Avenue and Benson Lane to improve existing traffic conditions and provide pedestrian and cycle crossing at Blaxland Road.

### Environment

The Santa Rosa Precinct provides opportunity for ecological restoration and protection in a number of locations and includes the following:

- Remediation of the existing lookout and WSUD feature on the eastern side of Santa Rosa Park
- Introduced bush regeneration and weed removal programs that includes public involvement to educate the community
- Enhancing identified vegetation communities with vegetation

species that belong to those communities as identified by the NSW Department of Planning and Environment and the City of Ryde

- Revegetation with native species where appropriate and provide creekline stabilisation where required to reduce erosion
- Enhanced fauna habitat for targeted species where appropriate with habitat boxes, hollow creation, translocated hollows, and other measures that also provide stepping-stones along the corridors, particularly in areas with little or no hollows
- Undertake restoration works to enhance aquatic habitat for frog and native fish in high conservation value waterways / corridors.
- Protection of habitat by controlling run-off entering sites if it has the potential to detrimentally change water, nutrient or sediment levels or cause erosion.
- Continued Gross Pollutant Trap maintenance and rubbish removal as currently conducted to help maintain and improve Rapid Riparian Assessment results
- Undertake a transition to more suitable path lighting for fauna around natural areas
- Expansion of the The Habitat community nursery

All works to existing facilities and the implementation of new facilities throughout this precinct all provide an opportunity to introduce additional native trees, shrubs, and grasses to enhance and expand on existing local ecologies.

### Recreation & Culture / Community

In this precinct, ELS Hall Park provides a range structured and informal sporting opportunities as well as a range of community facilities. The interconnectedness and activation of these open spaces through the implementation of a shared user path will provide safe, and enjoyable walking and cycling facilities for the local community. This Masterplan includes the following community facility upgrades at Santa Rosa Park:


- New multi-purpose community building that supports existing community groups such as the Scouts, Australian Air League, sporting clubs as well as other community groups. This will be situated in a similar location to the existing community building (entry off Quarry Road).
- District level playground with nature play, BBQ facilities, shade structures and filtered water stations.
- Fitness stations and bike repair stations
- Additional vehicle parking off Quarry Road and Bridge Road
- Upgrades to the sports grounds at Santa Rosa Park including sport field lighting and additional space for junior sports

Where applicable designs near Sydney Water assets (eg. Santa Rosa Park) will adhere to the following points:

- Where possible, the existing surface levels of the Sydney Water corridor will be retained.
- Shared user paths and/or pedestrian paths are recommended to be asphalt paths.
- The necessary technical reports and assessments will be commissioned during the detailed design phases to ensure the Sydney Water's services, assets and infrastructure are considered and not impacted upon during Masterplan implementation.
- Crime Prevention Through Environmental Design (CPTED) strategies will be implemented to ensure the space is safe and accessible.

This Masterplan, in conjunction with the ELS Hall Park, Greenwood Park, and Booth Reserve Masterplan, includes community facility upgrades at ELS Hall Park and surrounding parklands:

- Ryde Community Sports Centre to include additional indoor courts to meet demand
- Activation of lands not owned by Council, formalisation and integration of lands into the parklands
- Youth zone on the Epping Road/Whitecross Street frontage (including BMX/mountain bike track, skate/scooter park, multi-use court, picnic shelters, toilets and parking).
- Improve on-site parking and increase capacity to better meet demand by formalising new car park (entry off Kent Road). This may offer some parking relief for the adjoining Kent Road Public School community.
- Decommissioning the informal parking area (entry off Adelphi Road) and integration of this area back into ELS Hall Park for recreational use.



Section B - Santa Rosa Park, Bridge Road and Flinders Park



Precedent image - District level playground



Precedent image - Shade structures



Precedent image - Upgrades to sporting grounds





Precedent image - Upgraded pedestrian / cycle connections

## Beattie Park



## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment




# Santa Rosa Park




## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment



# Tindarra Reserve



## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment




# ELS Hall Park



# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Waterway
-  Existing Canopy Cover
-  Planting treatment



## 3.3 Macquarie Park Precinct

Shrimptons Creek has historically been impacted by the urbanisation of Macquarie Park. The open creek line is visible up to Waterloo Road. Shrimptons Creek travels beneath the centre of Macquarie Park. As such, the Shrimptons Creek Green Link is disconnected.

Shrimptons Creek and other adjoining minor watercourses reforms to the north of the M2 Motorway in Lane Cove National Park. Some low use and informal walking tracks / trails are in these areas. These areas have been included in the Shrimptons Creek Green Link corridor for general reference. There is potential opportunity for Council to work corroboratively with relevant stakeholders in the future to investigate feasibility to strengthen and improve these connections, tracks and trails.

### Green Transport

The Masterplan aims to connect currently fragmented pathways, capitalising on the existing network of off-road shared user paths to create a safe and continuous pedestrian and cycle link. Future connections in this precinct include:

- Connection to the existing off-road shared user path on Waterloo Road
- Connection to the existing off-road shared user path on both sides of the M2 Motorway linking to the Hills and North Ryde.
- Potential track connection between Dunholm Reserve and Shrimptons Creek Track
- Path lighting between ELS Hall Park / Greenwood Park to Waterloo Road to facilitate safe use beyond daylight hours.
- Opportunity for future investigation of feasibility for potential northern crossing points of Lane Cove River, pending consultation with relevant stakeholders and further investigations.

### Environment

The Macquarie Park precinct aims to improve the condition of Shrimptons Creek through the use of stormwater management strategies, creek stabilisation works, riparian corridor improvements and bush regeneration.

### Recreation & Culture / Community

The design facilitates connections to various existing and proposed parks and developments, offering a wide range of recreation opportunities and amenities. The proposed design along Shrimptons Creek adjacent to the Midtown Masterplan includes:

- Bridge crossings over Shrimptons Creek and viewing platforms
- New playground and skate park
- Connections into Midtown
- New filtered water station, bike repair station and bike racks



Precedent image - Bridge crossing over Shrimptons Creek and viewing platforms



Precedent image - Filtered water station



Precedent image - Improved health of Shrimptons Creek





Precedent image - New playground and skate park

# Macquarie Park



## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment




# Lane Cove River



**LEGEND**

- |   |   |  |
|---|---|--|
|  Site Boundary       |  Proposed Concrete Pathway       |  Waterway              |
|  Green Link route    |  Signalled road crossing         |  Existing Canopy Cover |
|  On-Road Cycle Route |  Pedestrian/ cycle road crossing |  Planting treatment    |





# 4.0 MASTERPLAN COUNTY GREEN LINK



## **Overview**


This Green Link is named after the County Road Corridor road reservation [reserved for a future road which has not been realised]. This corridor links Macquarie Park to Eastwood. The vision for this link is to provide a connected green open space network for recreation, active transport, ecology, culture, and interconnectivity between current and future public transport options.

## **Woorang Precinct**

Between Kent Road and Graham Avenue.

## **Eastwood Precinct**

Between Graham Avenue and Eastwood station.



**LEGEND**

- Precinct boundary
- Open green space
- Waterways
- Building footprint

## 4.1 Woorang Precinct

The Woorang precinct involves the activation of an underutilised open space land reservation between ELS Hall Park and Welby Street to provide a continuous off-road shared cycle route for both pedestrians and cyclists connecting ELS Hall Park to the Eastwood Precinct.

### Green Transport

The Green Links Masterplan ties into the City of Ryde's Masterplan for ELS Hall Park, continuing the off-road shared user path along Kent Road and Herring Road to join the open space land reservation between Abuklea Road and Welby Street. New raised crossings at key intersections along this route will provide safe crossing points for both cyclists and pedestrians, enhancing usage and connectivity along the route.

Additional off-road shared user paths will be implemented on:

- Woorang Street along the verge
- Welby Street, Edgar Street and Blaxland Road coming into Eastwood Precinct.
- Path lighting between ELS Hall Park to Welby Street to facilitate safe use beyond daylight hours.

### Environment

- The activation of the open space land reservation between Abuklea Road and Welby Street will provide an opportunity to protect and enhance existing vegetation within the corridor, creating a biodiversity corridor.
- The Masterplan provides connections to adjacent open spaces including Jim Walsh Park.

### Recreation & Culture / Community

The Masterplan provides a key connection to Jim Walsh Park, which acts as a recreation node and rest stop along the Green Link. In addition to the existing playground and public toilets, new additions to Jim Walsh Park include:

- Fitness station
- Filtered water station, bike repair station, bike rack
- Upgrade to the existing car park
- Upgraded park entry from Balaclava Road



Precedent image - Pedestrian / cycle improvements



Precedent image - Off-road shared user path



Precedent image - Fitness equipment




Precedent image - Improved biodiversity

## Abuklea Road to Kent Road



# LEGEND

- Site Boundary
- Green Link route
- On-Road Cycle Route
- Proposed Concrete Pathway
- Signalled road crossing
- Pedestrian/ cycle road crossing
- Waterway
- Existing Canopy Cover
- Planting treatment





## Grove Street to Abuklea Road




## LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment




## Blaxland Road to Grove Street



# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Waterway
-  Existing Canopy Cover
-  Planting treatment



## 4.2 Eastwood Precinct

The Eastwood Precinct is a key destination along the Masterplan, acting as the connector between the County and Terrys Creek Green Links. A series of strategies have been implemented to enhance connectivity to the Eastwood Town Centre [east and west], Eastwood train station and Eastwood Oval. Vehicle speed limits in this area will be reviewed, particularly on May Street and Railway Parade where the existing on-road cycle route will continue.

### Green Transport

The main route through this area utilises a shared user path along Blaxland Road, First Avenue, over the Rutledge Street overpass bridge, and along an on-road route down West Parade to the Eastwood Town Centre West and Eastwood Oval.

It is noted that there are two existing underpass tunnels beneath the railway line for pedestrians and dismounted cyclist. These links facilitate movement between the eastern and western side of Eastwood. The northern tunnel provides direct connection to the Eastwood train station and the bus interchanges on both sides of Eastwood station. The southern tunnel and the wall of Eastwood Library have existing colourful mural to encourage use, provide place-making and promote Eastwood's cultural inclusiveness. Both sides of Eastwood Station have pre-existing bicycle racks.

The Masterplan upgrades will include the following:

- New off-road shared user path along First Avenue
- Extending the existing shared user path along Blaxland Road to the May Street intersection
- Upgrading the existing pedestrian crossing on Railway Parade

### Environment

All works to existing facilities and the implementation of new facilities throughout this precinct all provide an opportunity to introduce additional native trees, shrubs, and grasses to enhance and expand on existing local ecologies.

### Recreation & Culture / Community

Enhancing pedestrian and cyclist crossings throughout this precinct will create a safe and accessible link to adjacent open spaces such as Eastwood Oval, with the inclusion of a new bike repair station in addition to the existing toilet block, playground and filtered water station.



Precedent image - Enhancing local ecologies



Precedent image - Improved pedestrian / cycle crossings




Precedent image - Off-road shared user path

# Eastwood



# LEGEND

- Site Boundary
- Green Link route
- On-Road Cycle Route
- Proposed Concrete Pathway
- ●  
● Signalled road crossing
- ▨  
▨  
▨ Pedestrian/ cycle road crossing
- Waterway
- Existing Canopy Cover
- Planting treatment





# 5.0 MASTERPLAN TERRYS CREEK GREEN LINK



Terrys Creek Walk

Browns Waterhole

## Overview

Terrys Creek forms an important regional biodiversity corridor, connecting to Lane Cove National Park. While recreational paths and boardwalks are provided through this area, the main focus is environmental; to protect and enhance the existing ecology.

The Terrys Creek walking track is for use by pedestrians and bush walkers. To protect the ecologically sensitive area, bicycles use is not permitted on the Terrys Creek walking track.

Through the implementation of the Green Links Masterplan, Council will progressively review the track network to strengthen the primary track. If/where required, Council will rationalise any duplicate routes, unnecessary sections of track and close any informal tracks. Where necessary boardwalks, delineation and steps may be incorporated in sections to reduce ecological impacts from track users.

The Green Links Masterplan seeks to formalise the short section of the missing link in the Terrys Creek walk [between Forrester Park and Forsyth Park] to provide a continuous bush walking link from Eastwood to Lane Cove National Park.

Terrys Creek Green Link cycle route via Vimiera Road to Browns Waterhole and northern connection onwards to Ku-ring-gai Council local government area provides an important local and regional active transport route. This Green Link connects with the

existing off-road shared user path network to Macquarie Park. The shared user path missing link between Epping Road and Waterloo Park will be addressed via the Masterplan.

The steep gradient of the shared user path to/from Browns Waterhole is a constraint. The section of shared user path to/from Browns Waterhole is a very scenic route through the National Park, however, the absence of path lighting (due to ecological reasons) discourages the use of this active transport route in the early morning and evening. Browns Waterhole is also flood prone and high rain events can result in closure of the shared user path.


New active transport link over Terrys Creek [near Abuklea Road] will strengthen local and regional routes between City of Ryde and City of Parramatta local government areas.

### Pembroke Precinct

From Forrester Park and the M2 Motorway, east of Terrys Creek and along Pembroke Park and Lucknow Park.

### Browns Waterhole Precinct

From north of the M2 Motorway underpass to Macquarie Park, via Browns Waterhole.



**LEGEND**

- Precinct boundary
- Open green space
- Waterways
- Building footprint

## 5.1 Pembroke Precinct

The Pembroke Precinct connects Eastwood to Epping Road through a series of bush tracks and bridges. Upgrades to these bush tracks will link into previously upgraded tracks that seek to formalise the missing link between Forrester Park and Forysth Park. These upgrades will include clear signage and entries into the reserves and enhancing on-road cycle routes will strengthen the connectivity of the Terrys Creek Green Link as well the accessibility to County and Shrimptons Creek Green Link.

### Green Transport

Pedestrian and cyclist movement throughout this precinct is facilitated through the upgrading of existing bush tracks and an adjacent on-road cycle route on both sides of Vimiera Road. Key shared user paths between Epping Road and Waterloo Road are realised as well as connections over Terrys Creek to Essex Street (creek crossing points and pedestrian bridge between Vimiera Road & Davis Avenue) and Forrester Park and Abuklea Road at Pembroke Park.

Cycling links via on-road cycle routes along Vimiera Road. This provides direct links to:

- M2 cycle route.
- M2 underpass which connects to Browns Waterhole shared user path in Lane Cove National Park.
- Macquarie Park and Macquarie University via off-road shared user paths on Waterloo Road, Culloden Road and Talavera Road.

New active transport link over Terrys Creek via Abuklea Road linking City of Ryde and City of Parramatta, and providing interconnectivity.

### Environment

Ecological restoration along this area includes key biodiversity habitats, therefore flora and fauna protection measures such as bushcare and creek stabilisation is aimed to promote responsible use of and adhere to wildlife protection areas.

### Recreation & Culture / Community

This network of pedestrian and cycle routes links together numerous existing parks to provide a series of interconnected, high quality open spaces offering a range of passive and active recreation opportunities. Pedestrian bush tracks provide a place for relaxation and reconnection with nature for the community.

Forrest Park provides a playground and outdoor social space for picnics and passive recreation, surrounded by a bushland setting. The masterplan proposes the installation of a small self-contained public toilet facility for park users and walkers on the Terrys Creek Walk.





Protect and enhance existing ecologies

# Forrester Park




# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Bush Walking Track
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Track - Creek Crossing/ Steps
-  Waterway
-  Existing Canopy Cover
-  Planting treatment
-  Track - Bridge




# Forsyth Park



# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Bush Walking Track
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Track - Creek Crossing/ Steps
-  Waterway
-  Existing Canopy Cover
-  Planting treatment
-  Track - Bridge




# Pembroke Park



# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Bush Walking Track
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Track - Creek Crossing/ Steps
-  Waterway
-  Existing Canopy Cover
-  Planting treatment
-  Track - Bridge



## 5.2 Browns Waterhole Precinct

Browns Waterhole is where Terrys Creek and the Lane Cove River converge. On both sides of Browns Waterhole, the shared user path travels down a modestly wide ravine within a relatively steep topography. The concrete path crosses the low point at Browns Waterhole via concrete pipes and weir, which are flood prone and from time to time result in the closure of this active transport route.

It is noted that the Greater Sydney Commission has identified Browns Waterhole as a future planning priority for improvement. As this is an area that involves multiple landowners and multiple Council areas, City of Ryde will seek to work collaboratively with relevant stakeholders for future investigations into the feasibility to strengthen and improve the connection via Browns Waterhole, and/or future investigations into other potential alternative routes to the north which could potentially be considered more viable.

### Green Transport


The Terrys Creek Link forms an important and well established ecological and recreational corridor linking to Lane Cove National Park. The aim for this precinct is to improve the accessibility and connectivity within the Terrys Creek Green Link as well as linking to both the County and Shrimptons Creek Link. This is achieved by increasing legibility of access points into parks and Lane Cove National Park, and strengthening connections through the use of new off-road shared user paths and on-road cycle routes. Existing bush tracks will be repaired and upgraded to ensure a seamless journey throughout the bushland.

### Environment

The main focus is to protect and enhance the existing ecology through bushcare and creek stabilisation works. This will re-establish Terrys Creek as an critical and connected biodiversity corridor within Ryde.

### Recreation & Culture / Community

The Browns Waterhole precinct provides a series of paths and boardwalks connecting existing bushland and adjacent parks such as Waterloo Park, offering a range of recreational facilities. As such, this precinct acts as a key recreation and leisure space for the local community and region.




Protect and enhance existing ecologies

# Lucknow Park



# LEGEND

-  Site Boundary
-  Green Link route
-  On-Road Cycle Route
-  Bush Walking Track
-  Proposed Concrete Pathway
-  Signalled road crossing
-  Pedestrian/ cycle road crossing
-  Track - Creek Crossing/ Steps
-  Waterway
-  Existing Canopy Cover
-  Planting treatment
-  Track - Bridge





## Browns Waterhole



# LEGEND

- Site Boundary
- Green Link route
- On-Road Cycle Route
- Bush Walking Track
- Proposed Concrete Pathway
- Signalled road crossing
- Pedestrian/ cycle road crossing
- Track - Creek Crossing/ Steps
- Waterway
- Existing Canopy Cover
- Planting treatment
- Track - Bridge




# Waterloo Park



# LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment
 Bush Walking Track	 Track - Creek Crossing/ Steps	 Track - Bridge



## 5.3 Interconnection - Browns Waterhole and Macquarie Park

The Terrys Creek Green Link strengthens the existing cycle route between Vimiera Road and Browns Waterhole. The Masterplan includes a new missing link shared user path missing link between Epping Road and Waterloo Road (via Marsfield Park).

The Terrys Creek Green Link cycle route (from Vimiera Road) has a strong interconnection to Waterloo Park with entries to the Park being provided from the Vimiera Road, Waterloo Road and Busaco Road.

The Terrys Creek cycle/pedestrian route (from Vimiera Road) provides interconnectivity with Macquarie University and Macquarie Park via an existing network of shared user paths in Waterloo Park, along Waterloo Road, Culloden Road and Talavera Road.

The Busaco Trail in the Lane Cove National Park provides an additional interconnecting pedestrian (bushwalking) route between Browns Waterhole and Macquarie Park. The existing Busaco Trail extends from Browns Waterhole to the northern end of Busaco Road. The pedestrian interconnection to Macquarie Park is achieved via existing footpath along Busaco Road and existing footpath/shared user path along Talavera Road.

The Green Links Masterplan identifies the future investigations to establish the feasibility to strength the existing active transport connection via Browns Waterloo (as the route gets cut off in high rain events) and/or investigate the feasibility for other potential routes to provide northern connections for active transport purposes over Lane Cove River. This will require an ongoing collaborative approach between the City of Ryde, relevant land owners and government agencies.



Elevated path through sensitive environment at Browns Waterhole



Bush track at Browns Waterhole



Protect and enhance existing environments



Existing shared user path at Browns Waterhole




Simple wayfinding

# TG Miller Sportsground



# LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment
 Bush Walking Track	 Track - Creek Crossing/ Steps	 Track - Bridge




## Marsfield Park



# LEGEND

 Site Boundary	 Proposed Concrete Pathway	 Waterway
 Green Link route	 Signalled road crossing	 Existing Canopy Cover
 On-Road Cycle Route	 Pedestrian/ cycle road crossing	 Planting treatment
 Bush Walking Track	 Track - Creek Crossing/ Steps	 Track - Bridge




# Busaco Road



# LEGEND

- |   |   |  |
|---|---|--|
|  Site Boundary       |  Proposed Concrete Pathway       |  Waterway              |
|  Green Link route    |  Signalled road crossing         |  Existing Canopy Cover |
|  On-Road Cycle Route |  Pedestrian/ cycle road crossing |  Planting treatment    |
|  Bush Walking Track  |  Track - Creek Crossing/ Steps   |  Track - Bridge        |







## 6.0 GIS ANALYSIS

## GIS Overview

Geographic Information System (GIS) analysis was undertaken to measure the walkability and cyclability that the Green Link improvements will provide throughout the City of Ryde local government area.


Calculations were taken from four key nodes throughout the City of Ryde local government area [Meadowbank Train Station, Macquarie Centre, Eastwood Train Station, Browns Waterhole], these nodes are within the three Green Links corridors.

At each node, a 30-minute walkability radius was calculated based on an average walking speed of 5km/hr. Using the existing pedestrian/cycle networks and the future routes of the Green Links, measurements were taken to understand the difference in travel distance post-completion of the Green Links Masterplan. The below images demonstrate the 30-minute walking radius post Green Links Masterplan completion.

The implementation of continuous shared paths and upgraded road crossings that form the Green Links Masterplan will provide local pedestrian/cycle-friendly routes that connects four key nodes, interconnection between the Green Link corridors and other destinations throughout the City of Ryde local government area and regional routes into adjoining local government areas.




Green Link - 30 minute walking radius from Eastwood train station.



Green Link - 30 minute walking radius from Browns Waterhole.



Green Link - 30 minute walking radius from Meadowbank train station.



Green Link - 30 minute walking radius from Macquarie Centre.

- Walking Radius - 30 minute
- Green Link
- Green Open Space
- Road Network
- Primary Connection Points
- Bus Stops





- Walking Radius - 30 minute
- Green Link Routes
- Green Open Space
- Road Network
- On road cycle route

GIS Overview - Active Transport Route calculations along Green Links pedestrian/ cycle networks and onward distances to adjoining locations



SHRIMPSTONS CREEK GREEN LINK				
From	To	Distance (km)	Travel Time Cycling (min)	Travel Time Walking (min)
Macquarie Park	Santa Rosa Park	2.4	9	31
Macquarie Park	West Ryde Station - Bike (via Heath St on-road cycle route & Anzac Ave)	5.3	18	64
Macquarie Park	West Ryde Station - Walk (via Heath St on-road cycle route & Carara Reserve)	5.8	N/A	70
Macquarie Park	MEEP (school site) via Heath St on-road cycle route	5.9	17	73
Macquarie Park	Meadowbank Station via Heath St on road cycle route	6.1	20	81
Macquarie Park	Meadowbank Wharf via Heath St on-road cycle route	6.6	22	93
Macquarie Park	Ryde Central/Top Ryde (via Heath St on-road cycle route & Parkes Street)	6.2	21	89
Macquarie Park	Melrose Park Light Rail (future – via Heath St on-road cycle route & Ryde River Walk)	10.1	31	121
Macquarie Park	Parramatta CBD (via Heath St on-road cycle route, Ryde River Walk & Parramatta Valley Cycleway)	16.2	54	194
Macquarie Park	Rhodes (via Heath St on-road cycle route & John Whitton Bridge)	7.7	25	92
Macquarie Park	Sydney Olympic Park (via Heath St on-road cycle route, John Whitton Bridge, Rhodes & Bicentennial Park)	13.8	46	175

COUNTY GREEN LINK				
From	To	Distance (km)	Travel Time Cycling (min)	Travel Time Walking (min)
Eastwood Station	Jim Walsh Park	1.4	4	17
Eastwood Station	ELS Hall Park	3.7	11	44
Eastwood Station	Macquarie Park (via Shrimptons Creek)	4.6	14	55

TERRYS CREEK GREEN LINK				
From	To	Distance (km)	Travel Time Cycling (min)	Travel Time Walking (min)
Eastwood Station	Forrester Park	1.1	3	13
Eastwood Station	Browns Waterhole – Walk (via Terrys Creek Walking Track)	5.33	N/A	57
Eastwood Station	Browns Waterhole - Bike (via Vimiera Road)	4.99	13	43
Eastwood Station	Macquarie Park - Bike (via Vimiera, Waterloo, Culloden and Talavera Roads)	6.7	20	80
Eastwood Station	Epping Aquatic Centre (via new active transport bridge/Pembroke Park)	2.3	7	27
Eastwood Station	Turrumurra (walk via Browns Waterhole)	9.63	29	117
Eastwood Station	Turrumurra - Bike (via Browns Waterhole)	9.29	28	111
Eastwood Station	Pymble - Walk (via Terrys Creek Walking track to Browns Waterhole)	10.33	31	124
Eastwood Station	Pymble - Bike (via Vimiera Road to Browns Waterhole)	9.99	30	120
Eastwood Station	Macquarie Park - Walk (via Busaco Trail, Busaco Road & Talavera Road)	8.73	N/A	105





**7.0** PRECEDENT IMAGES &  
DESIGN GUIDELINES

# 7.1 Planting Palette

The original vegetation communities along the Green Links Masterplan are described in the City of Ryde Biodiversity Plan [adopted in December 2016]. There are 22 different vegetation communities in the City of Ryde local government area, the Green Links Masterplan corridor includes the following:

- Blue Gum High Forest
- Coastal Enriched Sandstone Dry Forest
- Coastal Sandstone Gully Forest
- Coastal Sandstone Gallery Rainforest
- Sydney Turpentine-Ironbark Forest

In general, it is recommended that vegetation along the Green Links corridor should be selected from these original vegetation communities. This will enhance Councils vision to further increase tree canopy cover. Water Sensitive Urban Design [WSUD] opportunities in the form of swales, wetlands and bioretention systems should reference the City of Ryde Water Sensitive Urban Design Guidelines [adopted in May 2015].

Terrys Creek Green Link will be formed as a natural area biodiversity corridor, this will include endemic species from mid storey to understorey planting that consider unique habitat value. Continue bush care and bush regeneration works for land owned or under Council's care and control. It is noted that National Parks and Wildlife Service are responsible for the lands that form Lane Cove National Park.

Shrimptons Creek and County Green Links will create an urban biodiversity corridor with endemic species, including mid storey and understorey plantings with habitat values throughout the parklands. Plant species in the proximity of Sydney Water assets will be low lying with a shallow root profile to mitigate impacts on sub-terrain Sydney Water assets, whilst maintaining good sight lines.

The Green Links Masterplan promotes the use of the interconnecting routes between the three Green Links, especially for active transport. It is encouraged to provide additional tree canopy cover along interconnecting routes between the Green Links (eg. Abuklea Road).

## Freshwater wetlands

Freshwater wetlands for both habitat and stormwater treatment purposes are proposed at several locations along the Green Links corridors. Wetland plants are classified according to the water depth. Most wetlands should include a range of depths and high species diversity.

### Ephemeral zone

- *Carex apressa* [Tall Sedge]
- *Cyperus polystachyos* [Umbrella Grass]
- *Eleocharis gracilis* [Spike Rush]
- *Ficinia nodosa* [Knobbly Club-rush]
- *Isolepis inundata* [Swamp Club-sedge]
- *Juncus usitatus* [Common Rush]

- *Lepidosperma laterale* [Variable Sword Sedge]

### Shallow marsh

- *Carex fascicularis* [Tassel Sedge]
- *Eleocharis acuta* [Rush]
- *Ficinia nodosa* [Knobbly Club-rush]
- *Isolepis inundata* [Swamp Club-sedge]
- *Juncus usitatus* [Common Rush]
- *Persicaria* spp.
- *Triglochin striatum* [Streaked Arrowgrass]

### Marsh

- *Bolboschoenus caldwellii* [Sea Club Rush]
- *Bolboschoenus fluviatilis* [Rush]
- *Myriophyllum crispatum*
- *Schoenoplectus mucronatus* [Star Club Rush]
- *Schoenoplectus validus* [River Club Rush]

### Deep marsh

- *Baumea articulate* [Jointed Twig Rush]
- *Bolboschoenus fluviatilis* [Rush]
- *Eleocharis sphacelata* [Giant Spike Rush]
- *Schoenoplectus littoralis*
- *Schoenoplectus validus* [River Club Rush]

### Pools

- *Chara* spp. [Muskgrass]
- *Myriophyllum caput-medusae*
- *Myriophyllum verrucosum*
- *Potamogeton crispus* [Floating Pondweed]
- *Potamogeton ochreateus* [Blunt Pondweed]
- *Potamogeton pectinatus* [Fennel-leaved Pondweed]
- *Potamogeton tricarlinatus* [Floating-leafed Pondweed]
- *Vallisneria spiralis* [Tape Grass]

## Bioretention systems

Bioretention systems for stormwater treatment are proposed at some locations along the Green Link corridors. Typical species recommended for bioretention systems include:

- *Imperata cylindrica* [Blady Grass]
- *Ficinia nodosa* [Syn. *Isolepis nodosa*] [Knobbly Club Rush]
- *Juncus usitatus* [Common Rush]
- *Lomandra longifolia* [Spiny Matrush]
- *Poa affinis* [Tussock grass]
- *Themeda australis* [Kangaroo Grass]
- *Dianella caerulea* [Blue flax-lily]

Most species from Sandstone Forest and Heath communities are also likely to be appropriate in bioretention systems.

## Vegetation Communities

**Blue Gum High Forest (BGHF)** - is found on a range of shale-influence substrates in deep clay soils, with a high average rainfall between 900 and 1300mm. In the Ryde area BGHF is listed as a Critically Endangered Ecological Community and is found on south facing, steep slopes and gullies. The most significant areas of BGHF can be found in Denistone, Eastwood and West Ryde. It is estimated that over 95% of BGHF in the Sydney Basin region has been cleared.

**Coastal Enriched Sandstone Dry Forest** - is commonly encountered on the upper slopes and dry gullies of Sydney urban areas. It is a tall open eucalypt forest with an understorey of dry sclerophyll shrubs with ferns and herbaceous flowering plants amongst the ground cover. It is widespread on the Hornsby plateau and in areas that receive greater than 1000 millimetres of average annual rainfall.

**Coastal Sandstone Gully Forest** - Coastal Sandstone Gully Forest is commonly found along Sydney sandstone plateaus. It occupies sheltered aspects on infertile Hawkesbury sandstone in areas that receive more than 1000 millimetres of average annual rainfall. These rocky environments feature canopy trees such as Sydney Peppermints and Sydney red gums, with a diverse understorey of heath and shrub species such as banksias, tea-trees and wattles. In the Ryde Local Government Area Coastal Sandstone Gully Forest can be found along Terrys Creek, Kittys Creek, Pages Creek and the Lane Cove River.

**Coastal Sandstone Gallery Rainforest** - is a warm-temperate rainforest found on sandy alluvium or rocky streams in deep protected sandstone gully systems across the greater Sydney

region. These are rainforests of low species diversity compared to more complex rainforests associated with richer soils. The array of vines and climbers that are common in other rainforest assemblages are absent here. Instead, the ground cover is an open cover of ferns amongst sandstone boulders and fallen logs. It occurs in higher rainfall zones greater than 900mm per annum. This community grows in sheltered gullies, slopes and hillsides on Hawkesbury Sandstone. In the Ryde Local Government Area the remaining pockets of Coastal Sandstone Gallery forest can be found along Terrys Creek, Kittys Creek and the Lane Cove River.

**Sydney Turpentine-Ironbark Forest** - is a tall open forest found on shale and shale enriched sandstone soils. Sydney Turpentine-Ironbark Forest is listed as a Critically Endangered Ecological Community, with only 0.5 percent its original extent remaining intact. It consists of a mid-section of shrubs and small trees, with a grassy ground cover. The canopy consists mainly of turpentine, red mahogany and various Ironbark species. This vegetation community has a mean annual rainfall between 900 and 1250 mm.

### Key

- Bg = Blue Gum High Forest
- Cf = Coastal Sandstone Gully Forest
- Cs = Coastal Enriched Sandstone Dry Forest
- Cr = Coastal Sandstone Gallery Rainforest
- Si = Sydney Turpentine-Ironbark Forest
- t = trees
- st = small trees
- s = shrubs
- g = groundcovers, grasses and low shrubs (<0.5m)
- vc = vines and climbers

Table 1. Endemic plant species found within the City of Ryde.

Species Name	Common Name	Growth Form	Plant Community	Plant Images
<i>Acacia implexa</i>	Hickory	st	Bg	
<i>Acacia longifolia</i>	Sydney Golden Wattle	s	Cr/Cs	
<i>Acacia parramattensis</i>	Parramatta Wattle	s	Cr/Cs	
<i>Acacia suaveolens</i>	Sweet Wattle	s	Cs / Cf	
<i>Acacia terminalis</i>	Sunshine Wattle	s	Cs / Cf	

Species Name	Common Name	Growth Form	Plant Community	Plant Images	
<i>Acacia ulicifolia</i>	Prickly Moses	s	Cs		
<i>Acmena smithii</i>	Lilly Pilly	st	Bg/Cr		
<i>Allocasuarina littoralis</i>	Black She-oak	st	Cs		
<i>Angophora costata</i>	Sydney Red Gum	t	Cs/Si		
<i>Aristida vagans</i>	Threeawn Speargrass	g	Si		
<i>Austromyrtus tenuifolia</i>	Narrow Leaf Myrtle	s	Cr		
<i>Backhousia myrtifolia</i>	Grey Myrtle	st	Bg		
<i>Banksia serrata</i>	Old-man Banksia	st	Cs / Cf		
<i>Banksia spinulosa</i>	Hairpin Banksia	s	Cs		
<i>Billardiera scandens</i>	Apple Dumplings	vc	Cs/Si		
<i>Breynia oblongifolia</i>	Coffee Bush	s	Bg/Si		
<i>Bursaria spinosa</i>	Blackthorn	s	Si		
<i>Callicoma serratifolia</i>	Black Wattle	t	Cr		

Species Name	Common Name	Growth Form	Plant Community	Plant Images	
<i>Calochlaena dubia</i>	False Bracken Fern	g	Cr		
<i>Cassytha pubescens</i>	Devil's Twine	vc	Cs/Cr		
<i>Cayratia clematidea</i>	Native Grape	vc	Bg		
<i>Ceratopetalum apetalum</i>	Coachwood	t	Cr		
<i>Ceratopetalum gummiferum</i>	Christmas Bush	st	Cs / Cf		
<i>Cissus Antarctica</i>	Water Vine	vc	Bg		
<i>Clematis glycinoides</i>	Old Man's Beard	vc	Bg		
<i>Clerodendrum tomentosum</i>	Hairy Clerodendrum	st	Bg		
<i>Corymbia gummifera</i>	Red Bloodwood	t	Cs		
<i>Dianella caerulea</i>	Blue Flax-lily	g	Bg/Cs/Si/Cf		
<i>Dichondra repens</i>	Kidney Weed	g	Bg/Si		
<i>Dodonaea triquetra</i>	Large-leaf Hop-bush	s	Cs/Si		
<i>Doodia caudata</i>	Small Rasp Fern	g	Cr		

Species Name	Common Name	Growth Form	Plant Community	Plant Images	
<i>Echinopogon caespitosus</i> <i>var. caespitosus</i>	Bushy Hedgehog-grass	g	Si		
<i>Elaeocarpus reticulatus</i>	Blueberry Ash	st	Bg/Cs		
<i>Entolasia marginata</i>	Bordered Panic	g	Bg/Si		
<i>Entolasia stricta</i>	Wiry Panic	g	Cs/Si/Cf		
<i>Eucalyptus Acmenoides</i>	White Mahogany	t	Bg		
<i>Eucalyptus paniculata</i>	Grey Ironbark	t	Bg		
<i>Eucalyptus paniculata</i> subsp. <i>paniculata</i>	Grey Ironbark	t	Si		
<i>Eucalyptus pilularis</i>	Blackbutt	t	Bg/Cs/Si		
<i>Eucalyptus piperita</i>	Sydney Peppermint	t	Cs		
<i>Eucalyptus resinifera</i>	Red Mahogany	t	Si		
<i>Eucalyptus saligna</i>	Sydney Blue Gum	t	Bg		
<i>Eustrephus latifolius</i>	Wombat Berry	vc	Bg/Si		
<i>Glycine clandestina</i>	Love Creeper	g	Si		

Species Name	Common Name	Growth Form	Plant Community	Plant Images
<i>Glycine microphylla</i>	Small-leaf glycine	vc	Bg/Si	
<i>Hibbertia aspera</i> <i>subsp. aspera</i>	Rough Guinea Flower	s	Si	
<i>Juncus usitatus</i>	Common Rush	g	Cr	
<i>Lepidosperma laterale</i>	Variable Sword-sedge	g	Si / Cf	
<i>Leptospermum polygalifolium</i> <i>subsp.</i>	Yellow Tea Tree	s	Cr	
<i>Leptospermum trinervium</i>	Flaky-barked Tea-tree	s	Cs / Cf	
<i>Leucopogon juniperinus</i>	Prickly Beard-heath	s	Bg/Si	
<i>Lomandra longifolia</i>	Spiny-headed mat-rush	g	Bg/Cs/Cr/Si/Cf	
<i>Lomandra multiflora</i>	Many-flowered Mat-rush	g	Si	
<i>Lomatia silaifolia</i>	Crinkle Bush	s	Cs / Cf	
<i>Maytenus silvestris</i>	Narrow-leaved Orange Bark	s	Bg	
<i>Melaleuca linariifolia</i>	Flax-leaved Paperbark	t	Cr	
<i>Microlaena stipoides</i> <i>var. stipoides</i>	Weeping Grass	g	Si/Bg/Cs	

Species Name	Common Name	Growth Form	Plant Community	Plant Images	
<i>Morinda jasminoides</i>	Sweet Morinda	vc	Cr/Bg		
<i>Notelaea longifolia</i>	Mock-olive	s	Bg/Si		
<i>Oplismenus aemulus</i>	Basket Grass	g	Bg/Cr		
<i>Oplismenus imbecillis</i>	Creeping Beard Grass	g	Bg		
<i>Ozothamnus diosmifolius</i>	Paper Daisy	s	Bg/Si		
<i>Pandorea pandorana</i>	Wonga Wonga Vine	vc	Bg/Si		
<i>Persoonia levis</i>	Broad-leaved Geebung	s	Cs / Cf		
<i>Pittosporum revolutum</i>	Yellow Pittosporum	s	Bg/Si		
<i>Poa affinis</i>	Native Tussock Grass	g	Bg		
<i>Polyscias sambucifolia</i>	Elderberry Ash	s	Bg/Si		

Species Name	Common Name	Growth Form	Plant Community	Plant Images	
<i>Pratia purpurascens</i>	Whiteroot	vc	Si/Bg		
<i>Pseuderanthemum variable</i>	Pastel Flower	g	Bg/Si		
<i>Pteridium esculentum</i>	Bracken Fern	g	Cs		
<i>Smilax glycyphylla</i>	Sweet Sarsparilla	vc	Cs / Cf		
<i>Syncarpia glomulifera</i>	Turpentine	t	Bg/Cs/Si		
<i>Themeda australis</i>	Kangaroo Grass	vc	Si		
<i>Trema tomentosa</i>	Native Peach	s	Bg		
<i>Tristaniopsis laurina</i>	Water Gum	t	Cr		
<i>Tylophora barbata</i>	Bearded Tylophora	vc	Bg/Si		
<i>Xanthosia pilosa</i>	Woolly Xanthosia	g	Cs / Cf		

## 7.2 Materials Palette

This section outlines the recommended treatments, materials and finishes along the Green Links corridor including street furniture, paving, lighting, fencing and wayfinding.

The key objective is to achieve a consistent and integrated suite of public domain elements which bind together the precincts, promoting consistency and clarity throughout the Green Links.

### Paving / paths

Along the Green Links a variety of path types have been proposed:

- On-road cycle route
- Off-road shared user path
- Separated cycle lane
- Footpaths
- Elevated boardwalks
- Bridge crossings
- Bush tracks

### Signage

Signage along the Green Links corridor should include different styles for different purposes, including:

- Simple wayfinding
- Detailed wayfinding
- Regional bike route signage
- Shared user paths
- Separated cycle lane
- Custom graphics
- Informative
- Interpretive
- Bushland/ natural area specific signage in compliance with Council's overall Park Signage Strategy

### Wayfinding signage

Wayfinding signage can either be simple, designed to be read quickly while moving, or more detailed, typically including a map, designed for route planning.

General recommendations for wayfinding signage are:

- Use a distinct style with Green Links branding to clearly identify the Green Links from other routes
- Include signage with destination and distance markers to promote use, local and regional connectivity as well as interconnective routes.
- Limit signage to locations where it is necessary, or where it adds valuable information
- Locate signage where it is visible and easily readable
- Maintain a consistent application of signage along the Terrys Creek Walk throughout track head signs

### Instructive signage

Instructive signage helps indicate where people should walk or ride and how they should behave.

### Interpretive signage

Interpretive signage can be used to describe the narrative of a space. Historical, cultural and ecological stories can be shared along the Green Link Links through interpretive signage.

## Lighting

Along the Green Links, proposed lighting is recommended to be pole mounted lighting. Bollard lighting may be appropriate to use along secondary paths. Informal paths are intended to be unlit. Where appropriate, alternative path lighting may be considered in ecologically sensitive areas to minimise impacts on local flora and fauna.

Lighting strategy will be informed by City of Ryde's Park Lighting policy.

## Furniture

Selected furniture should be robust, incorporate accessible design principles and require minimum maintenance. Furniture should suite the urban, park and bush characters of the Green Links. All elements are minimalist and non-intrusive / not distracting from the setting in which it is located. Furniture elements include the following:

- Bike racks
- Street furniture
- Picnic shelters
- BBQs
- Filtered water stations (with dog bowls)
- Water bubblers
- Bin enclosures

## Fencing

Fencing may be required in bush regeneration / protection areas where the restriction of pedestrian movement is needed.

Log delineations may also be a natural option along bush tracks and/or natural areas.

### Main path – Off-road shared user path

Where the main path can be constructed off-road, a minimum 3.5 m wide concrete path is recommended. It should function as a shared user path, indicated with signage and pavement marking. This path should include lighting. The surface needs to be adequately smooth and non-slip, to suit all users.

Material:

- insitu / full width format lightly exposed aggregate concrete with grey oxide or asphalt
- Bitumen finish for shared user paths in close proximity to Sydney Water Assets to allow for access and serviceability.



Precedent image - off-road shared user path [Culloden Road, Marsfield - existing on Terrys Creek Green Links]

### Main path – elevated <0.4 m

Where the main path passes through sensitive environments, it should be elevated up to 0.4 m above ground level. Handrails are not required at <0.4 m above ground level. It should function as a shared user path (where applicable), indicated with signage and pavement marking. This path should include lighting. Its minimum width is recommended as 3.5 m.

Material: Fibre Reinforced Plastic [FRP] decking.



Precedent image - elevated <0.4m [Narrabeen lagoon]

### Bush track – elevated >0.4 m

Where bush tracks pass over steep ground, steel mesh crossings or Fiber Reinforced Plastic [FRP] may be used to achieve safe and robust pedestrian crossings.

Material: Fibre Reinforced Plastic [FRP] decking or steel mesh with galvanised steel handrails.



Precedent image - elevated >0.4m

### On-road – separated cycleway (bidirectional)

On some streets a separated cycleway is recommended. This is a bike-only path, located between the pedestrian footpath and the road.

Minimum width [bidirectional cycleway] = 2.4 m + 0.4 m kerb

Material: asphalt road pavement with a green surface.



Precedent image - Typical City of Sydney separated cycleway

### On-road – separated cycleway (unidirectional)

On some streets a separated cycleway is recommended. This is a bike-only path, located between the pedestrian footpath and the road on either side of the street.

Where some roads narrow the separated cycleway should function as unidirectional, indicated with signage and pavement marking.



Precedent image - Unidirectional separated cycleway [Campbell Street, Sydney]



Precedent image - On road bike boulevard

### On-road – bike boulevard

Where the main Green Links route is along a quiet street, it is recommended that the street be designed as a “bike boulevard”, designed for shared bike and vehicle use.

Material: asphalt road pavement with a coloured surface.

A 30 km/hr speed limit is recommended in these streets.



Precedent image - On-road cycle route [Vimiera Road, Marsfield - existing on Terrys Creek Green Links]

### On-road – Cycle Route

Where on-road routes have been identified, a mixed traffic environment has been recommended.

A mixed traffic street should include pavement markings to highlight the likely presence of bikes. These should be located centrally in each lane to indicate the safest place to ride.



Precedent image - Paved shared zone in Bundra Street, ACT

### On road – shared zones

Shared zones accommodate mixed pedestrian, bike and vehicle traffic at low speeds.

Only applicable where Transport for NSW guidelines warrant their use.

Shared zones are typically designed with a distinct paved surface [e.g. concrete or asphaltic unit pavers] more typical of a footpath than a road.



Precedent image - Redfern secondary shared user path

### Secondary paths

Secondary paths may be 1.5-3.5 m wide, depending on their expected use. A pedestrian only path can be as little as 1.5 m wide. For a shared user path, 2.0 m is recommended as a minimum width. Secondary paths may also be either at-grade or elevated, with materials recommended as above for the main path.

Secondary paths may or may not include lighting.



Precedent image - Parramatta Park unpaved path

### Informal paths

Where paths are proposed through natural areas [e.g. ecological restoration sites], informal paths have been recommended. A suggested width is 1.0 m.

A natural, permeable surface is recommended, e.g. crushed sandstone. No lighting is recommended.

## Directional signage

At appropriate locations, use a distinct style with Green Links branding to clearly identify the Green Links from other routes.



Precedent image - Directional signage [GreenWay - Inner West Council wayfinding sign]

## Simple wayfinding – vertically mounted

Where there are existing poles or vertical elements where wayfinding signs can be mounted, signs should be located at eye level for pedestrians/bike riders, be easy to read and include brief, essential information. The wayfinding information in these signs should be local – e.g. street names and local destinations.



Precedent image - Vertically mounted signage [Frome bikeway, Adelaide SA]

## Simple wayfinding – integrated in pavement

To avoid a proliferation of poles and signposts, simple wayfinding signage can also be integrated in pavements. This example on the kerb is printed in a location where wear will be minimal.



Precedent image - Signage integrated in pavement [Frome bikeway, Adelaide SA]

## Detailed wayfinding – map based

Map-based wayfinding signs should be provided at regular intervals to assist with navigation. Maps should show important local and regional destinations and should help people navigate between the Green Links corridor and other places within walking and riding distance.



Precedent image - Detailed map based wayfinding [Sydney]

## Regional bike route signage

In NSW there is an established style for signage of regional bike routes, shown here. This style of signage would be appropriate where the Green Links connects to other regional or local routes.

However this signage style may be considered inappropriate as a template for the Green Links Masterplan itself – it tends to denote distant rather than local destinations and is typically installed too high to be easily visible while walking or riding.



Precedent image - Typical NSW regional bike route signage



Precedent image - Bourke Street cycle way

### Pedestrian / Cycle Crossings

Where pedestrian / cycle routes cross local streets, it is recommended that raised wombat crossings are used to provide safe and visible crossing points for shared path users. Planting should be included where appropriate to enhance local ecologies.



Precedent image - Shared user path graphics [City of Sydney]

### Shared user path graphics

Shared user paths are typically indicated in the City of Sydney with:

- Blue shared user path symbols
- Blue text
- Blue edges and sometimes, scattered spots


It is recommended that this style should be adopted along the Green Links as it is well understood throughout the Greater Sydney area.



Precedent image - Separated cycleways are typically indicated with bike signs and arrows [City of Sydney]

### Separated cycleways graphics

Separated cycleways are typically indicated with bike signs and arrows.



Precedent image - Custom pavement detail

### Custom graphics

Custom graphics can stand out and help to encourage positive behaviours.



Precedent image - Interpretive sign [GreenWay - Inner West Council wayfinding sign]

### Interpretive signage - informative

Interpretive signage can share a layer of information about a space that would usually go unrecognised.

### Interpretive signage - evocative and informative

Interpretive signage can include a mixture of evocative and informative elements. This style of signage is designed both to attract interest and share information.



Precedent image - Shorebirds interpretive sign at Penrhyn Estuary

### Interpretive signage - evocative

Some interpretive signage is light on text but uses materials, imagery and other artistic elements to evoke information about a place. This style of signage is designed as a prominent feature to attract attention and inspire interest.



Precedent image - Interpretive signage at Botany Bay

### Path lighting - pole mounted

For the Green Links Masterplan, path pole-mounted lights with LED (or equivalent future technology) would be appropriate for the main Green Link shared user paths. CPTED principles to be applied. This style of lighting is highly directional on the path to minimise lighting spill on surrounding areas.



Precedent image - Pole-mounted lighting

### Tunnels

Lighting is particularly important in tunnels to improve safety at night. Utilise safer-by-design approaches, with a focus on place-based, integrated outcomes. Artwork in the form of lighting / murals is recommended for these spaces.



Precedent image - Tunnel lighting

### Bike racks

Steel U shaped bike racks have been installed through out the City of Ryde local government areas, similar styled bike racks should be used to maintain consistency through out the Green Links corridor.



Precedent image - Existing steel bike racks at Lewisham West



Precedent image - Street furniture; metal seating (parks)  
powder coated steel frame with oiled hardwood timber slats (natural areas)




Precedent image - filtered water station



Precedent image - Street bin enclosure



Precedent image - Metal bike repair station with tyre pump and tools



Precedent image - Post and single rail fence [Stewart Park, Marsfield]

## Seating

Typical seats should be consistent with park and urban domain furniture used throughout the City of Ryde local government area.

## Filtered water stations / Bubblers

Filtered water stations / bubblers should be consistent with park and urban domain assets used throughout the City of Ryde local government area.

## Bins

Bins should include paired litter and recycling bins and should be consistent with park and urban domain assets used throughout the City of Ryde local government area.

## Bicycle Repair Station

Bicycle repair stations should be consistent with park and urban domain assets throughout the City of Ryde local government area

## Fencing of ecological restoration sites

Where fencing is required the preferred option is recommended to be as unobtrusive as possible. Post and single metal rail is recommended and should be consistent with similar fencing throughout the City of Ryde local government area.

Around these fences, native vegetation should be planted either side to minimise visibility of the fence and to enhance ecological values.



The background of the page is a close-up photograph of a green, textured pavement surface, likely a bicycle lane. White markings are visible, including a bicycle symbol at the top, a chevron arrow pointing right, and the word "STOPS" written in large, bold, sans-serif letters at the bottom. The text "8.0 IMPLEMENTATION PLAN" is centered in the upper half of the image.

## 8.0 IMPLEMENTATION PLAN

# 8.1 Implementation Plan

This Implementation Plan is a high level overview providing the City of Ryde and key stakeholders with a methodology to achieve progressive implementation of the Green Links Masterplan over a 20 year period.

The more specific details and descriptors of the individual Masterplan elements are featured throughout Section 3-5 of this Report. These provide a benchmark for the extent of the stages/upgrades that make up this Masterplan.

The individual Masterplan elements have been put designated into logical small groupings to form stages/upgrades for progressive Masterplan implementation. This has considered factors such as geographic location, strategic importance, safety considerations, elements which have the potential to be implemented concurrently and/or project scale for incorporation into Council's planning and delivery plan.

Within the "Project/Strategic Value and Implementation Matrix" in the following pages, the various stages/upgrades of the Green Links Masterplan have been reviewed and allocated a "Project Value" score based on each of the Green Links Masterplan project values (0 – nil, 1 – low, 2 – medium, 3 – high). This assessment has considered the strategic location, proximity to existing program / amenity and maximum potential in achieving the Masterplan vision.

Each stage/upgrade has been scored based on the positive impact it will have in achieving the Masterplan vision as well as addressing the following four key project themes:

**Green Transport:** the Green Links as a transport corridor

**Environment:** the Green Links as blue and green biodiversity corridors

**Recreation & Culture / Community:** the Green Links as a place that meets multiple recreational needs and is a focal point for community and culture


Each stage/upgrade has been further reviewed and assigned a level of "Strategic Importance" (Low/Medium/High) and "Implementation Priority" (Short, Medium and Long term).

**Strategic Importance:** This categorisation has considered whether the stage/upgrade provide will yield local (City of Ryde), regional (adjoining local government areas and/or greater metropolitan Sydney) and/or environmental strategic benefits/connections when implemented. This assessment has considered a range of other strategies, plans, other current/future Masterplan and upgrades as prepared by Greater Sydney Commission, NSW Government, the City of Ryde and other stakeholders.

**Implementation Priority:** Each stage/upgrade has been further reviewed and allocated a level of "Implementation Priority" (Short, Medium and Long term). In very general terms, implementation time frames can be anticipated to be approximately short term (1 – 5 years), medium term (5 – 10 years) and long term (10 – 20 years). Note: these time frames are indicative only and may be subject to change and/or variation.

The "Project Implementation Priorities" table are intended to be a guidance/reference tool to assist Council when determining future implementation priorities, budget allocations for individual Masterplan stages/upgrades and/or future grant funding applications.

Implementation of the various stages/projects of the Green Links Masterplan will be subject to availability of funding. Where required, further consideration, consultation and formalisation of agreements will be undertaken between Council, land owners (eg. Transport for NSW and Sydney Water) and stakeholders for the overall Green Links Masterplan (once adopted) and for the respective stages/upgrades contained within. Detailed design and where required, the necessary technical reports, feasibility studies and/or approvals will be obtained in due course for the applicable Masterplan stages/upgrades.




# SHRIMPTONS CREEK GREEN LINK

## Implementation Priority of Meadowbank/ West Ryde Precinct Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES (0 - Nil, 1 - Low, 2 - Medium, 3 - High)				STRATEGIC IMPORTANCE (Local, Regional, Environmental)	IMPLEMENTATION PRIORITY (Short, Medium, Long)
	GREEN TRANSPORT	ENVIRONMENT	RECREATION & CULTURE	VALUE SCORE		
1.1.2   New bike repair station (Memorial Park)	2	1	2	4	Medium - local & regional	Short term
1.1.8   New local playground (Helene Park)	0	0	3	3	Medium - local	Short - Medium term
1.2.1   Opportunity for improved traffic flow between eastern and western side of Meadowbank train station and Bank Street	2	0	1	3	Medium - local	Medium - Long term
1.2.2   Opportunity for greater pedestrianisation (near Meadowbank Station)	2	0	1	3	Medium - local	Medium - Long term
1.2.4   Off-road shared user path through MEEP	3	0	3	6	High - local & regional	Short term Refer to MEEP Masterplan
1.2.5   Existing overpass bridge - opportunity to pedestrianise (Angas St)	2	0	1	3	Medium - local	Medium - Long term
1.2.6   New off-road shared user path (See Street)	3	0	2	5	Medium - local	Medium - Long term
1.2.8   1.2.10   1.2.12   1.2.14   Opportunity for improved pedestrian route (refer MEEP)	2	0	1	3	Medium - local	Short - Medium term Refer to MEEP Masterplan
1.2.16   Opportunity for improved pedestrian and cycle route (refer MEEP)	2	0	1	3	Medium - local & regional	Short - Medium term Refer to MEEP Masterplan
1.2.13   1.2.17   Strengthen blue and green links (refer MEEP)	2	0	1	3	Medium - local	Short - Medium term Refer to MEEP Masterplan
1.2.15   Enhance connectivity with underpass beneath railway line (refer MEEP)	2	0	1	3	Medium - local	Short - Medium term Refer to MEEP Masterplan
1.3.1   New pedestrian and cycle overpass above Victoria Rd	2	0	2	4	High - local & regional	Short - Medium term Refer to MEEP Masterplan
1.3.5   Upgrade footpath to shared path & tie into MEEP Masterplan	2	0	0	2	Medium - local & regional	Short term / In progress
1.3.7   New bus zone (Ryedale Rd)	2	0	0	2	Medium - local & regional	Short term / In progress
1.3.9   New raised threshold crossing (Ryedale Rd)	2	0	0	2	Medium - local & regional	Short term / In progress
1.3.11   Investigate potential for future pedestrian / cycle route along T9 rail corridor to Epping	2	0	0	2	Medium - local & regional	Medium - Long term
1.3.15   New off-road shared user path (Wattle St)	3	0	1	4	High - local & regional	Medium - Long term
1.3.16   1.4.1   New separated cycle path from West Ryde (Anzac Ave)	3	0	1	4	High - local & regional	Medium-Long term
1.3.10   1.3.17   1.3.21   New raised pedestrian/ cycle road crossing (Anzac Ave, Wattle St and Ryedale Rd)	3	0	1	4	Medium - local & regional	Medium - Long term
1.3.18   1.4.2   New separated cycle path to West Ryde	3	0	1	4	High - local & regional	Medium - Long term
1.3.19   New off-road shared user path (Anzac Ave)	3	0	1	4	High - local & regional	Medium - Long term
1.3.23   New off-road shared user path (Hermitage Rd)	3	0	1	4	High - local & regional	Short term Refer to MEEP Masterplan
1.3.22   Future Active Transport Connection (Herbert St)	2	0	1	3	Medium - local	Medium - Long term
1.3.26   1.3.25   Existing traffic intersection - recommended for detailed traffic analysis and review of phasing, vehicle turning from Hermitage Rd and bike / pedestrian crossing (Victoria Rd)	2	0	1	3	High - local & regional	Medium term
1.4.4   New raised pedestrian crossing (Goodwin St)	2	0	0	2	Medium - local & regional	Short term - Medium term
1.4.5   Upgrade existing local playground (Carara Reserve)	0	1	1	2	Low - local	Medium - Long term
1.4.7   Potential fitness station within Carara Reserve	0	1	1	2	Low - local	Medium - Long term
1.3.20   Bike repair Station (Anzac Park)	2	0	1	3	Medium - local & regional	Short term
1.4.6   Filtered water station and rest stop (Carara Reserve)	0	1	1	2	Low - local	Medium - Long term
1.4.10   1.4.11   Pedestrian path with path lighting (Carara Reserve and Benson Lane)	2	0	0	2	Medium - local & regional	Short - Medium term




# SHRIMPTONS CREEK GREEN LINK

## Implementation Priority of Santa Rosa Precinct Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMENT	RECREATION & CULTURE	VALUE SCORE		
1.5.2   New signalised pedestrian/ cycle crossing (intersection design subject to detailed traffic analysis) (Blaxland Rd)	3	0	2	5	High – local & regional	Short-Medium term
1.5.4   Upgrade existing local playground (Beattie Park)	0	1	1	2	Medium – local	Medium term
1.6.1   New raised pedestrian crossing with separated cycle crossing (Quarry Rd)	2	0	0	2	Medium – local & regional	Short term
1.6.2   Existing carpark – to be upgraded (Santa Rosa Park)	0	0	2	2	Medium – local	Medium term
1.6.3   Existing habitat Nursery to be extended and playground relocated (Santa Rosa Park)	0	3	2	5	Medium – local & environmental	Medium term
1.6.5   1.6.22   Existing community building to be decommissioned. Existing use to be accommodated in new community building (refer 1.6.15)	0	0	3	2	Medium – local	Medium term
1.6.6   Filtered water station and bike repair station (Santa Rosa Park)	2	1	2	4	Medium – local & regional	Medium term
1.6.7   Fitness station (Santa Rosa Park)	1	0	2	3	Medium – local	Short term - Medium term
1.6.8   District Playground, BBQ and picnic shelters (Santa Rosa Park)	0	0	3	3	Medium – local	Short term/ in progress
1.6.9   Native vegetation corridor (Santa Rosa Park)	1	3	1	5	Medium – local, regional & environmental	Medium term
1.6.10   Native vegetation and bush regeneration zone (Santa Rosa Park)	0	3	0	3	Medium – environmental	Medium term
1.6.11   1.6.13   Multi-purpose sportsground (grass) with drainage upgrade and sports field lighting (Santa Rosa Park)	0	0	3	3	Medium	Short - Medium term
1.6.12   Widen existing off-road shared user path with path lighting (Santa Rosa Park)	2	1	3	6	Medium – local & regional	Medium term
1.6.15   New multipurpose community building (including accessible community hall with kitchenette, café/kiosk, public toilets, sports change rooms x2, storage, outdoor undercover area, water storage tanks and bike racks (Santa Rosa Park)	0	0	3	2	Medium – local	Medium term
1.6.20   WSUD opportunity (Santa Rosa Park)	0	2	0	2	Medium – environmental	Medium term
1.6.23   Widen existing off-road shared path and re-route around fitness station (Santa Rosa Park)	2	1	3	6	Medium – Local & regional	Medium term
1.6.24   Expand existing car parking (Santa Rosa Park)	0	0	2	2	Medium – local	Medium term
1.6.25   New path connection between 2 x Bridge Rd entries (Santa Rosa Park)	2	0	1	3	Medium – local	Medium term




# SHRIMPTONS CREEK GREEN LINK

## Implementation Priority of Santa Rosa Precinct & ELS Hall Park Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMNET	RECREATION & CULTURE	VALUE SCORE		
1.7.1   Future stormwater, creek stabilisation, riparian corridor and bush regeneration zones (Flinders Park)	0	3	0	3	Medium/High – environmental	Short - Medium ongoing
1.7.4   1.7.9   Widen existing off-road shared user path with path lighting (Flinders Park and Tindarra Reserve)	2	1	3	6	Medium – Local & regional	Medium term
1.7.8   Future stormwater, creek stabilisation, riparian corridor improved maintenance and bush regeneration zones (Tindarra Reserve)	0	3	0	3	Medium/High – environmental	Short - Medium ongoing
1.7.10   Creek stabilisation works (Tindarra Reserve)	0	3	0	3	Medium/High – environmental	Short - Medium & ongoing
1.7.2   Upgrade picnic shelters, BBQ and seating (Flinders Park)	0	0	2	2	Medium – local	Medium term
1.7.7   New dedicated cycleway using road reserve (Ford St)	2	0	1	3	Medium – local & regional	Medium term
1.7.15   New pedestrian/ cycle road crossing (Ford St)	3	0	2	5	Medium – local	Medium term
1.8.4   New cycle path on southern side of Scott St with new connection to existing shared user path	2	0	1	3	Medium – local & regional	Medium term
1.8.12   New bridge with shared user path crossing Shrimptons Creek to new Youth Zone	3	0	2	5	Medium – local	Medium – Long term
1.8.14   New Mountain bike/BMX track (Youth Zone)	2	1	3	6	High – local & regional	Short - Medium term
1.8.13   New picnic shelters (Youth Zone)					High – local & regional	Medium – Long term
1.8.15   New shared user path connecting to Epping Road cycleway with path lighting (Youth Zone)					High – local & regional	Medium – Long term
1.8.16   New multi-use court (Youth Zone)					High – local & regional	Medium – Long term
1.8.17   New skate/ scooter park (Youth Zone)					High – local & regional	Medium – Long term
1.8.18   New public toilets (Youth Zone)					High – local & regional	Medium – Long term
1.8.9   Upgrade existing pedestrian/ cycle underpass and/ or investigate feasibility for alternative long term strategy to mitigate flooding/ closure during high rain events (Epping Rd)	2	0	1	3	High – local & regional	Short – Medium term
1.8.19   Light well to underpass below (Epping Rd)	2	0	1	3	High – local & regional	Short – Medium term
1.8.20   New car parking (Youth Zone)	0	0	2	2	Medium – local	Medium term
2.1.11   New carpark recommended for integration into ELS Hall Park	0	1	2	3	Medium - local	Short - Medium term Refer to ELS Hall Park Masterplan
Bushcare and bush regeneration works	0	3	0	3	High - environmental	Ongoing




# SHRIMPSTONS CREEK GREEN LINK

## Implementation Priority of Macquarie Park Precinct Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMENT	RECREATION & CULTURE	VALUE SCORE		
1.8.22   Raised boardwalk (near Midtown)	2	3	1	6	High - local, regional & environmental	Short - Medium term Refer to Mid-town Masterplan
1.8.23   Upgrade existing off-road shared user path with path lighting (near Midtown)	2	1	1	6	Medium - local	Medium term
1.9.1   Bridge crossing (near Mid-town)	2	3	1	6	High - local, regional & environmental	Short - Medium term Refer to Mid-town Masterplan
1.9.3   Proposed skate park (Mid-town)	2	1	1	4	Medium - local	Short - Medium term Refer to Mid-town Masterplan
1.9.5   Outdoor fitness equipment - potential location (Mid-town)	2	1	1	4	Medium - local	Short - Medium term
1.9.8   Viewing platform (near Mid-town)	2	3	1	6	High - local, regional & environmental	Short - Medium term Refer to Mid-town Masterplan
1.9.10   Future stormwater, creek stabilisation, riparian corridor improvements and bush revegetation zone (near Wilga Park)	2	1	1	4	High - local & regional Medium - environmental	Short - Medium term Ongoing. Refer to Mid-town Masterplan
1.9.11   Upgrade off-road shared user path with path lighting (near Wilga Park/ Cottonwood Reserve)	2	1	1	4	High - local & regional Medium - environmental	Short - Medium term.
1.9.14   New filtered water station, bike repair station and bike racks (Waterloo Rd)	2	1	1	4	High - local & regional Medium - environmental	Short - Medium term.
1.10.10   Investigate feasibility to strengthen active transport route/s northern connections over Lane Cove River	2	0	0	2	Medium - local & regional	Medium term
Bushcare and bush regeneration works	0	3	0	3	High - Environmental	Ongoing




# COUNTY GREEN LINK

## Implementation Priority of County Precinct Projects



MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES (0 - Nil, 1 - Low, 2 - Medium, 3 - High)				STRATEGIC IMPORTANCE (Local, Regional, Environmental)	IMPLEMENTATION PRIORITY (Short, Medium, Long)
	GREEN TRANSPORT	ENVIRONMNET	RECREATION & CULTURE	VALUE SCORE		
2.1.2   New raised pedestrian and cycle crossing (Abuklea Rd)	3	0	2	5	Medium - local	Medium term
2.1.11   New carpark recommended for integration into ELS Hall Park	0	1	2	3	Medium - local	Short - Medium term. Refer to ELS Hall Park, Greenwood Park & Booth Reserve Masterplan
2.1.9   New pedestrian/ cycle road crossing (Herring Rd)	2	0	1	3	Medium/High - local & regional	Medium term
2.1.10   New off-road shared path (Kent Rd & Herring Rd)	2	0	1	3	Medium/High - local & regional	Medium term
2.1.3   New off-road shared user path with path lighting (Herring Rd - Abuklea Rd)	3	1	1	5	Medium/High - local & regional.	Short - Medium term
2.1.4   2.1.5   Native vegetation corridor (Agincourt - Abuklea Rd)	0	3	0	3	Medium - local, regional & environmental	Medium term
2.1.6   New raised pedestrian and cycle crossing (Agincourt Rd)	3	1	1	5	Medium/High - local	Short - Medium term
2.1.7   Park entry Fay Pl	1	0	2	3	Medium - local	Medium term
2.2.2   2.2.7   New raised pedestrian and cycle crossing (North Rd and Grove St)	3	0	1	4	Medium/High - local & regional.	Short - Medium term
2.2.3   New off-road shared user path lighting (North Rd and Grove St)	3	1	1	5	Medium/High - local & regional.	Short - Medium term
2.2.4   2.2.9   Native vegetation corridor (North Rd - Grove St)	0	3	0	3	Medium - local, regional & environmental.	Medium term
2.2.5   2.2.6   Opportunity for other community park elements and fitness station (North Rd - Grove St)	0	2	2	4	Medium - local	Medium - Long term
2.2.8   New off-road shared user path along verge (Woorang St)	3	0	1	4	Medium/High - local & regional.	Short - Medium term
2.2.10   Park entry Waratah St and interconnection to Denistone East Public School	2	0	2	4	Medium - local	Medium term
2.3.3   New fitness station (Jim Walsh Park)	0	0	2	2	Medium - local	Medium - Long term
2.3.4   Upgrade existing car park (Jim Walsh Park)	0	0	2	2	Medium - local	Medium term
2.3.5   Filtered water station, bike repair station and bike rack (Jim Walsh Park)	2	1	2	5	Medium - local & regional	Medium term
2.3.6   2.3.9   New raised pedestrian/ cycle crossing (Orange St & Graham Ave)	3	1	1	5	Medium/High - local & regional. Medium - environmental.	Short - Medium term
2.3.7   New bridge crossing (near Graham Ave)	3	1	1	5	Medium/High - local & regional.	Short - Medium term
2.3.8   New off-road shared user path with path lighting (Orange St - Graham Ave)	3	1	1	5	Medium/High - local & regional. Medium - environmental.	Short - Medium term
2.3.12   Improve park entry on Balaclava Rd frontage (Jim Walsh Park)	1	1	1	3	Low/Medium - local	Medium - Long term




# COUNTY GREEN LINK

## Implementation Priority of Eastwood Precinct Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMENT	RECREATION & CULTURE	VALUE SCORE		
2.3.1   New pedestrian/ cycle road crossing (Gordon St)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.3.2   New off-road shared user path along verge (Welby St)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.2   New bike repair station (Eastwood Park)	2	1	1	4	Medium – local	Short – Medium term
2.4.8   Upgrade existing pedestrian crossing (Railway Pde)	3	1	1	5	Medium/High – local	Short - Medium term
2.4.13   2.4.23   2.4.25   High pedestrian area. Vehicle speed limit to be reviewed (East Pde, Railway Pde & May St)	3	1	1	5	Medium/High – local & regional. Medium – environmental.	Short - Medium term
2.4.15   2.4.38   New raised pedestrian/ cycle crossing (East Pde & West Pde)	3	1	1	5	Medium/High – local	Short - Medium term
2.4.32   2.4.34   New off-road shared user path (Welby St & Edgar St)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.28   New off-road shared user path (Blaxland Rd)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.35   New pedestrian/ cycle road crossing (Edgar St)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.19   New off-road shared user path (First Ave)	3	0	1	4	Medium – Local & Regional.	Medium - Long term
2.4.21   New pedestrian/ cycle road crossing (Ryedale Rd)	3	0	1	4	Medium – Local & Regional.	Medium - Long term
2.4.24   New pedestrian/ cycle crossing (Ball Ave)	3	1	1	5	Medium/High – local	Short - Medium term
2.4.37   New off-road shared user path from Eastwood Station (May St & Railway Pde)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.39   New shared user path to/from Eastwood Station (East Pde)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
2.4.41   Investigate potential future pedestrian/ cycle route along T9 rail corridor to Epping	2	0	0	2	Medium – local & regional	Medium - Long term
2.4.42   New off-road shared user path to Eastwood Station (May St and Railway Pde)	3	0	1	4	Medium/High – Local & Regional.	Medium - Long term
Eastwood Station – general precinct upgrades (East Parade / Railway Parade/May Street)	2	0	1	3	Medium – Local & Regional.	Medium – Long term




# TERRYS CREEK GREEN LINK

## Implementation Priority of Pembroke Precinct Projects




MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMNET	RECREATION & CULTURE	VALUE SCORE		
3.1.12   Proposed toilet (Forrester Park)	2	1	2	5	Medium – local & environmental	Medium - Long term
3.1.13   3.1.14   3.2.19   New pedestrian path (Forrester Park)	2	1	2	5	Medium – local & environmental	Medium - Long term
3.1.15   Investigate potential for future pedestrian/ cycle route along T9 rail corridor to Epping	2	0	0	2	Medium – local & regional	Medium - Long term
3.2.5   Formalise the walking track to connect Forrester Park and link both sides of Forsyth Park	2	2	1	5	High – local & regional	Short – Medium term (subject to necessary negotiations)
3.2.9   Future pedestrian/ cycle connection between Abuklea Rd (City of Ryde) & Abuklea Rd (City of Parramatta). Refer LSPS	3	0	2	5	High – local & regional	Medium - Long term
3.2.16   Future pedestrian/ cycle bridge. Refer LSPS	2	1	2	5	Medium – local & environmental	Medium - Long term
Review and rationalise walking tracks. Decommission duplicate and informal tracks.	0	3	0	3	Medium - environmental	Ongoing
Bushcare and bush regeneration works	0	3	0	3	High - environmental	Ongoing



# TERRYS CREEK GREEN LINK

## Implementation Priority of Browns Waterhole Precinct to Macquarie Park Projects



MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES <i>(0 - Nil, 1 - Low, 2 - Medium, 3 - High)</i>				STRATEGIC IMPORTANCE <i>(Local, Regional, Environmental)</i>	IMPLEMENTATION PRIORITY <i>(Short, Medium, Long)</i>
	GREEN TRANSPORT	ENVIRONMNET	RECREATION & CULTURE	VALUE SCORE		
3.5.13   New off-road shared user path (Vimiera Road)	3	0	2	5	Medium – local & regional	Medium - long term
3.6.5   New bike repair station (Waterloo Park)	2	1	1	4	Medium – local	Short – Medium term
3.7.6   3.8.3   New off-road shared user path connecting Epping Rd and Waterloo Rd (Vimiera Rd)	3	0	2	5	Medium – local & regional	Medium - long term
3.8.4   Pedestrian / cycle crossing (Vimiera Rd)	3	0	2	5	Medium - local & regional	Medium - long term
Bushcare and bush regeneration works	0	3	0	3	High - environmental	Ongoing
3.9.4   Improve entry to Busaco Trail	2	1	1	4	Medium – local & environmental	Medium term
Investigate feasibility to improve Browns Waterhole for active transport route including flood mitigation during high rain events.	3	1	2	6	Medium/High – local & regional	Long term (subject to necessary investigations & negotiations)
Investigate feasibility for northern active transport connections over Lane Cove River.	3	1	2	6	Medium/High – local & regional	Long term (subject to necessary investigations & negotiations)



# 9.0 APPENDIX A

## 9.1 Shrimptons Creek Green Link (Blaxland Road - Quarry Road) Sections/ Plans not adopted by Council (26.07.2022)

The Green Links Masterplan and Report was adopted by Council at the Council Meeting on 26 July 2022. The Council resolution on 26 July 2022 excluded the use of the Sydney Water land reservation between Blaxland Road and Quarry Road from the Shrimptons Creek Green Link route. The Green Links Masterplan and Report was amended following the Council Meeting to reflect the exclusion of the Sydney Water land reservation between Blaxland Road and Quarry Road. Appendix A has been created for transparency and document control, to specifically identify which components of the draft Masterplan have not been adopted by Council.

## Concept Image

### Sydney Water land reservation: Blaxland Road - Quarry Road (not adopted by Council)



This Concept Image has been excluded from the Masterplan Report.



## Section Image

### Sydney Water land reservation: Blaxland Road - Quarry Road (not adopted by Council)

This section has been excluded from the Masterplan Report.





Section C - Shared User Path Through Sydney Water Land Reservation (not adopted by Council)

## Plans

### Sydney Water land reservation: Blaxland Road - Quarry Road (not adopted by Council)


Refer to page 54 - 55 for adopted version of this section of the Shrimptons Creek Green Link plans.






**LEGEND**

- Site Boundary
- Green Link route
- On-Road Cycle Route
- Proposed Concrete Pathway
- Signalled road crossing
- Pedestrian/ cycle road crossing
- Waterway
- Existing Canopy Cover
- Planting treatment






## Implementation Plan

### Sydney Water land reservation: Blaxland Road - Quarry Road (not adopted by Council)

Refer to page 140 for adopted version of this section of the Implementation Plan.



MASTERPLAN PROJECT/ STAGE FOR IMPLEMENTATION	PROJECT VALUES (0 - Nil, 1 - Low, 2 - Medium, 3 - High)				STRATEGIC IMPORTANCE (Local, Regional, Environmental)	IMPLEMENTATION PRIORITY (Short, Medium, Long)
	GREEN TRANSPORT	ENVIRONMNET	RECREATION & CULTURE	VALUE SCORE		
1.5.1   1.5.5   1.5.8   New off-road shared user path with path lighting (Sydney Water land reservation)	3	1	2	6	High – local & regional	Short term
1.5.2   New signalised pedestrian/ cycle crossing (intersection design subject to detailed traffic analysis) (Blaxland Rd)	3	0	2	5	High – local & regional	Short – Medium term
1.5.4   Upgrade existing local playground (Beattie Park)	0	1	1	2	Medium – local	Medium term
1.5.6   Native vegetation corridor (Sydney Water land reservation)	2	3	1	6	High - local, regional & environmental	Short term
1.5.7   New raised pedestrian/ cycle crossing point (North Rd)	3	1	2	6	High – local & regional	Short term
1.6.1   New raised pedestrian crossing with separated cycle crossing (Quarry Rd)	2	0	0	2	Medium – local & regional	Short term
1.6.2   Existing carpark – to be upgraded (Santa Rosa Park)	0	0	2	2	Medium – local	Medium term
1.6.3   Existing habitat Nursery to be extended and playground relocated (Santa Rosa Park)	0	3	2	5	Medium – local & environmental	Medium term
1.6.5   1.6.22   Existing community building to be decommissioned. Existing use to be accommodated in new community building (refer 1.6.15)	0	0	3	2	Medium – local	Medium term
1.6.6   Filtered water station and bike repair station (Santa Rosa Park)	2	1	2	4	Medium – local & regional	Medium term
1.6.7   Fitness station (Santa Rosa Park)	1	0	2	3	Medium – local	Short term - Medium term
1.6.8   District Playground, BBQ and picnic shelters (Santa Rosa Park)	0	0	3	3	Medium – local	Short term/ in progress
1.6.9   Native vegetation corridor (Santa Rosa Park)	1	3	1	5	Medium – local, regional & environmental	Medium term
1.6.10   Native vegetation and bush regeneration zone (Santa Rosa Park)	0	3	0	3	Medium – environmental	Medium term
1.6.11   1.6.13   Multi-purpose sportsground (grass) with drainage upgrade and sports field lighting (Santa Rosa Park)	0	0	3	3	Medium	Short - Medium term
1.6.12   Widen existing off-road shared user path with path lighting (Santa Rosa Park)	2	1	3	6	Medium – local & regional	Medium term
1.6.15   New multipurpose community building (including accessible community hall with kitchenette, café/kiosk, public toilets, sports change rooms x2, storage, outdoor undercover area, water storage tanks and bike racks (Santa Rosa Park)	0	0	3	2	Medium – local	Medium term
1.6.20   WSUD opportunity (Santa Rosa Park)	0	2	0	2	Medium – environmental	Medium term
1.6.23   Widen existing off-road shared path and re-route around fitness station (Santa Rosa Park)	2	1	3	6	Medium – Local & regional	Medium term
1.6.24   Expand existing car parking (Santa Rosa Park)	0	0	2	2	Medium – local	Medium term
1.6.25   New path connection between 2 x Bridge Rd entries (Santa Rosa Park)	2	0	1	3	Medium – local	Medium term

